

Exhibit A
RMRA Project List for 2025/2026 Fiscal Year

| Project Road | Project Location | Project Title | Project Type | Project Description | Pre-Construction Estimated Start | Pre-Construction Estimated Completion | Construction Estimated Start | Construction Estimated Completion | State Senate | State Assembly | Estimated Minimum Useful Life | Estimated Maximum Useful Life | Additional Project Elements |
|--------------------------|-----------------------------|--|-------------------------------------|--|----------------------------------|---------------------------------------|------------------------------|-----------------------------------|--------------|----------------|-------------------------------|-------------------------------|-----------------------------|
| Anderson Dr & College Rd | Multiple | ANDERSON DR & COLLEGE RD MAR 23 CATB | Road Maintenance | This project will include: Pavement Rehab/Repair (Existing) | 03/2023 | 03/2023 | 04/2023 | 08/2025 | 17 | 29 | 50 Years | 75 Years | No |
| Aptos Beach Rd | PM 0.00 | APTOS BEACH RD PM 0.00 | Other | Slipout onto RR, Downdrain damage | 03/2023 | 04/2023 | 03/01/2023 | 08/2025 | 17 | 29 | 50 Years | 75 Years | No |
| Bean Creek Rd | PM 0.25 | BEAN CREEK RD PM 0.25 | Other | This project will include: 110' long slipout undercutting existing cribwall. Recommend soil nail wall to stabilize slope | 03/2023 | 05/2025 | 04/30/2023 | 12/2025 | 17 | 29 | 50 Years | 75 Years | No |
| Bean Creek Rd | PM 1.87 | BEAN CREEK PM 1.87 | Other | Roadway Slipout, 50' long x 20' tall, Tree Fell due to unstable steep slope, A lot of groundwater near toe of failure. Soldier pile wall repair | 02/2023 | 04/2025 | 05/2025 | 12/2025 | 17 | 29 | 50 Years | 75 Years | No |
| Bean Creek Rd | PM 2.10 | BEAN CREEK PM 2.10 | Other | This project will include: Landscape Safety Rehab/Repair (Existing), Storm Drain and/or Culvert Rehab/Repair (Existing) Slipout (25+/-' L) - Recommend SB (Outboard) Shoulder Reconstruction, Drainage Improvements and Retaining Wall (Soldier Pile) Installation | 02/2023 | 04/2025 | 05/2025 | 12/2025 | 17 | 29 | 50 Years | 75 Years | No |
| Bean Creek Rd | PM 2.39 | BEAN CREEK RD PM 2.39 | Other | 24" cnp damaged and 20' of inlet crushed. Replace culvert and construct new headwalls | 02/2023 | 05/2026 | 06/2026 | 12/2026 | 17 | 29 | 50 Years | 75 Years | No |
| Bear Creek Rd | PM 0.20 | BEAR CREEK RD PM 0.20 | Other | This project will include: Pavement Rehab/Repair (Existing) Large Slipout (75' L) and Damaged 48" Culvert - Recommend EB and WB Traveled Way and Shoulder Reconstruction, Ramped Culvert and Headwalls and Retaining Wall (Soldier Pile) Installation | 03/2023 | 04/2023 | 03/01/2023 | 08/2025 | 17 | 29 | 50 Years | 75 Years | No |
| Bear Creek Rd | PM 3.41 | BEAR CREEK RD PM 3.41 | Other | This project will include: Storm Drain and/or Culvert Rehab/Repair (Existing) | 03/2023 | 04/2023 | 03/01/2023 | 08/2025 | 17 | 29 | 50 Years | 75 Years | No |
| Bear Creek Rd | PM 4.18 | Bear Creek Rd PM 4.18 | Other | Culvert Collapsed. Deformed from bottom. Approx. 4'. Jack and bore new culvert under roadway | 02/2023 | 05/2026 | 06/2026 | 12/2026 | 17 | 29 | 50 Years | 75 Years | No |
| Bear Creek Rd | PM 6.73 | Bear Creek Rd PM 6.73 | Other | This project will include repair of a Road edge slipout 60' x 60' | 03/2024 | 05/2027 | 06/2027 | 12/2027 | 17 | 29 | 50 Years | 75 Years | No |
| Bear Creek Rd | PM 7.41 | Bear Creek Rd PM 7.41 | Other | Road Edge slipped out 30' long. Recommend shoulder pile wall | 02/2023 | 05/2026 | 06/2026 | 12/2026 | 17 | 29 | 50 Years | 75 Years | No |
| Browns Valley Rd | PM 2.93 | Browns Valley Rd PM 2.93 | Other | Slipout (10' L) - NB Shoulder Reconstruction, RSP and Drainage Improvements | 02/2017 | 4/2025 | 5/2025 | 12/2025 | 17 | 29 | 50 Years | 75 Years | No |
| Browns Valley Rd | PM 3.17 | BROWNS VALLEY PM 3.17 | Other | 30' long slipout on edge of roadway. Soldier pile wall repair | 03/2023 | 06/2023 | 06/2023 | 08/2025 | 17 | 29 | 50 Years | 75 Years | No |
| Capitola Rd | 7th Ave to 17th Ave | Capitola Rd Widening from 7th Ave to 17th Ave | Other | Widen Capitola Rd from two lanes to four | 01/2023 | 12/2025 | 02/2026 | 01/2027 | 17 | 29 | 50 Years | 75 Years | No |
| Capitola Rd | Chanticleer Ave to 30th Ave | Capitola Rd Widening from Chanticleer Ave to 30th Ave | Other | Widen Capitola Rd from two lanes to four | 01/2023 | 12/2025 | 02/2026 | 01/2027 | 17 | 29 | 50 Years | 75 Years | No |
| Casserty Rd | PM 2.93 | Casserty Rd PM 2.93 | Other | Slipout (20' W x 80' L) - EB/SB Shoulder Reconstruction, Drainage Improvements and Retaining Wall (Soldier Pile) Installation | 02/2017 | 4/2025 | 5/2025 | 12/2025 | 17 | 30 | 50 Years | 75 Years | No |
| Casserty Rd | PM 3.39 | Casserty Rd PM 3.39 | Other | Slipout (20' W x 20' L) - EB/SB Shoulder Reconstruction and Drainage Improvements | 02/2017 | 4/2025 | 5/2025 | 12/2025 | 17 | 30 | 50 Years | 75 Years | No |
| Cathedral Dr | PM 1.21 | Cathedral dr PM 1.21 | Other | This project will include: Storm Drain and/or Culvert Rehab/Repair (Existing) | 02/2017 | 4/2025 | 5/2025 | 12/2025 | 17 | 30 | 50 Years | 75 Years | No |
| China Grade Rd | PM 0.62 | CHINA GRADE PM 0.62 | Other | Culvert failure washed out roadway. Temporary bridge placed until bottomless arch culvert can be placed | 01/2023 | 05/2026 | 01/30/2023 | 12/2026 | 17 | 29 | 50 Years | 75 Years | No |
| Countywide | All Roads | Countywide Roadway Culvert Survey | Other | Countywide Roadway Culvert Survey | 05/2020 | 07/2026 | - | - | 17 | 29 | 50 | 50 | No |
| Countywide | All Roads | Countywide Roadside Vegetation Maintenance Project | Road Maintenance and Rehabilitation | Countywide Roadside Vegetation Maintenance Project | 05/2020 | 07/2026 | - | - | 17 | 29 | 5 | 5 | No |
| Countywide | All Roads | Countywide Roadside Drainage Maintenance Project | Road Maintenance and Rehabilitation | Countywide Roadside Drainage Maintenance Project | 05/2020 | 07/2026 | - | - | 17 | 29 | 5 | 5 | No |
| Countywide | All Roads | Countywide Culvert Maintenance Project | Road Maintenance and Rehabilitation | Countywide Culvert Maintenance Project | 05/2020 | 07/2026 | - | - | 17 | 29 | 50 | 75 | No |
| Countywide | All Roads | Countywide Roadbed Maintenance Project | Road Maintenance and Rehabilitation | Countywide Roadbed Maintenance Project | 05/2020 | 07/2026 | - | - | 17 | 29 | 10 | 20 | No |
| Countywide | All Roads | Countywide Striping Maintenance Project | Safety | Countywide Striping Maintenance Project | 05/2020 | 07/2026 | - | - | 17 | 29 | 5 | 5 | No |
| Countywide | All Roads | Countywide Signage Maintenance Project | Safety | Countywide Signage Maintenance Project | 05/2020 | 07/2026 | - | - | 17 | 29 | 10 | 20 | No |
| Countywide | All Roads | Countywide Guardrail Maintenance Project | Safety | Countywide Guardrail Maintenance Project | 05/2020 | 07/2026 | - | - | 17 | 29 | 50 | 75 | No |
| Countywide | All Roads | Countywide Pavement Planning/Grinding | Road Maintenance & Rehabilitation | This project will include: Pavement Rehab/Repair (Existing),Paving and/or Striping Rehab/Repair (Existing Safety) | 05/2020 | 07/2026 | - | - | 17 | 29 | 50 Years | 75 Years | No |
| Cox Rd | PM 1.71 | COX RD PM 1.71 | Other | 160' long slipout halfway into road. Soldier pile repair | 01/2023 | 04/2023 | 04/30/2023 | 08/2025 | 17 | 29 | 50 Years | 75 Years | No |
| Cox Rd | PM 1.93 | COX RD PM 1.93 | Other | This project will include: Slipout (40' L) - Recommend WB Shoulder Reconstruction, Drainage Improvements (New Storm Drain Through Wall) and Retaining Wall (Soldier Pile) Installation | 01/2023 | 05/2027 | 06/2027 | 12/2027 | 17 | 29 | 50 Years | 75 Years | No |
| Cox Rd | PM 2.03 | COX RD PM 2.03 | Other | This project will include: Slipout (60'W x 100' L) - Recommend WB Traveled Way and Shoulder Reconstruction, Drainage Improvements, RSP and Retaining Wall (Soldier Pile) | 01/2023 | 04/2023 | 04/30/2023 | 08/2025 | 17 | 29 | 50 Years | 75 Years | No |
| Day Valley Rd | PM 1.18 | Day Valley Rd PM 1.18 at Cox Rd | Other | This project will include repair of a Road edge slipout 25' x 10' | 03/2024 | 05/2027 | 06/2027 | 12/2027 | 17 | 29 | 50 Years | 75 Years | No |
| E Zayante Rd | PM 1.01 | E Zayante Rd PM 1.01 | Other | This project will include repair of a Road edge slipout 20' x 40' | 03/2024 | 05/2027 | 06/2027 | 12/2027 | 17 | 29 | 50 Years | 75 Years | No |
| E Zayante Rd | PM 4.48 | E ZAYANTE PM 4.48 | Other | 15' long by 8' tall slipout on edge of road. Soldier pile repair | 01/2023 | 04/2023 | 3/15/2023 | 12/2027 | 17 | 29 | 50 Years | 75 Years | No |
| E Zayante Rd | PM 4.69 | E ZAYANTE PM 4.69 | Other | 70' long by 15' tall slipout 6' into roadway. 18" HDPE crossing at location. One lane closed. Soldier pile repair | 01/2023 | 04/2023 | 3/15/2023 | 12/2027 | 17 | 29 | 50 Years | 75 Years | No |
| E. Cliff Dr | 17th Ave to Palisades Ave | E. Cliff Dr Pedestrian Improvements from 17th Ave to Palisades Ave | Other | Construct pedestrian and bike improvements | 01/2023 | 06/2026 | 08/2026 | 01/2027 | 17 | 29 | 50 Years | 75 Years | No |
| E. Cliff Dr | 7th Ave to 14th Ave | E. Cliff Dr Pedestrian Improvements from 7th Ave to 14th Ave | Other | Construct pedestrian and bike improvements | 01/2023 | 06/2026 | 08/2026 | 01/2027 | 17 | 29 | 50 Years | 75 Years | No |
| Empire Grade | UCSC ARBORETU | EMPIRE GRADE @ UCSC ARBORETUM | Other | 40' long slipout on road shoulder. Geogrid reinforced slope repair | 01/2023 | 04/2023 | 01/30/2023 | 08/2025 | 17 | 29 | 50 Years | 75 Years | No |
| Eureka Canyon Rd | PM 0.35 | EUREKA CANYON PM 0.35 | Other | 40 foot long slipout, 3 ft into road. Soldier pile repair | 01/2023 | 04/0225 | 05/2025 | 12/2025 | 17 | 29 | 50 Years | 75 Years | No |
| Eureka Canyon Rd | PM 3.16 | Eureka Canyon Rd PM 3.16 | Other | Culvert Failure and Slipout (12' L) - SB (Outboard) Shoulder Reconstruction, Drainage Improvements including 36" Culvert Replacement and Retaining Wall (Soldier Pile) Installation | 02/2017 | 4/2025 | 5/2025 | 12/2025 | 17 | 29 | 50 Years | 75 Years | No |
| Eureka Canyon Rd | PM 3.36 | Eureka Canyon Rd PM 3.36 | Other | Major Slipout (20+/-' W x 70' L) with Potential Deep Seated Landslide - NB Traveled Way and Shoulder Reconstruction and Retaining Wall (Soldier Pile) Installation | 02/2017 | 4/2025 | 5/2025 | 12/2025 | 17 | 29 | 50 Years | 75 Years | No |
| Eureka Canyon Rd | PM 3.50 | Eureka Canyon Rd PM 3.50 | Other | Tree Fell on causing 25' long slipout on edge of roadway. RSP embankment repair | 03/2023 | 05/2025 | 05/2025 | 12/2025 | 17 | 29 | 50 Years | 75 Years | No |
| Eureka Canyon Rd | PM 4.28 | Eureka Canyon Rd PM 4.28 | Other | This project will include: Cost Estimating, Document Preparation, Environmental Study/Documents, Preliminary Design | 03/2023 | 05/2025 | 05/2025 | 12/2025 | 17 | 29 | 50 Years | 75 Years | No |

Exhibit A
RMRA Project List for 2025/2026 Fiscal Year

| Project Road | Project Location | Project Title | Project Type | Project Description | Pre-Construction Estimated Start | Pre-Construction Estimated Completion | Construction Estimated Start | Construction Estimated Completion | State Senate | State Assembly | Estimated Minimum Useful Life | Estimated Maximum Useful Life | Additional Project Elements |
|---------------------------|-----------------------------|--|-------------------------|---|----------------------------------|---------------------------------------|------------------------------|-----------------------------------|--------------|----------------|-------------------------------|-------------------------------|-----------------------------|
| Eureka Canyon Rd | PM 4.67 | Eureka Canyon Rd PM 4.67 | Other | Roadway/Embankment Settling (20' L) Caused by Fallen Trees and Near Existing Retaining Wall (Crib) - NB and SB Traveled Way and Shoulder Reconstruction, Drainage Improvements including RSP and Retaining Wall (Soldier Pile) Installation | 02/2017 | 4/2025 | 5/2025 | 12/2025 | 17 | 29 | 50 Years | 75 Years | No |
| Eureka Canyon Rd | PM 5.05 | Eureka Canyon Rd PM 5.05 | Other | Slipout (25' L) - SB Shoulder Reconstruction, Drainage Improvements, RSP and Retaining Wall (Soldier Pile) Installation | 02/2017 | 4/2025 | 5/2025 | 12/2025 | 17 | 29 | 50 Years | 75 Years | No |
| Eureka Canyon Rd | PM 5.31 | Eureka Canyon Rd PM 5.31 | Other | Slipout (25' L) - NB Shoulder Reconstruction, RSP and Retaining Wall (Soldier Pile) Installation | 02/2017 | 4/2025 | 5/2025 | 12/2025 | 17 | 29 | 50 Years | 75 Years | No |
| Eureka Canyon Rd | PM 5.33 | Eureka Canyon Rd PM 5.33 | Other | 25' long slipout, Rock wall repair with roadway reconstruction | 02/2017 | 05/2025 | 05/2025 | 12/2025 | 17 | 29 | 50 Years | 75 Years | No |
| Eureka Canyon Rd | PM 6.50 | Eureka Canyon Rd PM 6.50 | Other | This project will include: Cost Estimating, Document Preparation, Environmental Study/Documents, Preliminary Design, Right of Way | 02/2017 | 05/2025 | 05/2025 | 12/2025 | 17 | 29 | 50 Years | 75 Years | No |
| Eureka Canyon Rd | PM 8.39 | Eureka Canyon Rd PM 8.39 | Other | Slipout (50' L) - SB Shoulder Reconstruction, Drainage Improvements, RSP and Retaining Wall (Soldier Pile) Installation | 02/2017 | 4/2025 | 5/2025 | 12/2025 | 17 | 29 | 50 Years | 75 Years | No |
| Gaffey Rd | PM 0.03, 0.04, 0.08 | Gaffey Rd PM 0.03, 0.04, 0.08 | Other | Slipout (20' L) - EB (Outboard) Embankment Reconstruction, RSP and Drainage Improvements | 02/2017 | 05/2022 | 06/2026 | 12/2026 | 17 | 30 | 50 Years | 75 Years | No |
| Gaffey Rd | PM 0.08 | GAFFEY RD PM 0.08 | Other | Damaged culvert to be replaced. Includes fish passage. | 02/2023 | 05/2026 | 06/2027 | 12/2027 | 17 | 29 | 50 Years | 75 Years | No |
| Glen Canyon Rd | PM 0.39 | Glen Canyon Rd PM 0.39 | Other | Sink Hole found near culvert inlet. Slipline or replace culvert | 02/2023 | 05/2026 | 06/2026 | 12/2026 | 17 | 29 | 50 Years | 75 Years | No |
| Glen Haven Rd | PM 0.70 | GLEN HAVEN PM 0.70 | Other | Loss of road shoulder app. 100' long. Soldier pile repair. | 02/2023 | 05/2023 | 01/30/2023 | 08/2025 | 17 | 29 | 50 Years | 75 Years | No |
| Glenwood Cut-off | PM 0.02 | Glenwood Cut-off PM 0.02 | Other | Slipout (4' W x 35' L) - WB (Outboard) Traveled Way and Shoulder Reconstruction, Drainage Improvements and Retaining Wall (Crib) Installation | 02/2017 | 4/2025 | 5/2025 | 12/2025 | 17 | 29 | 50 Years | 75 Years | No |
| Glenwood Dr | PM 2.02 | Glenwood Dr PM 2.02 | Other | Erosion Under Existing Retaining Wall (Soldier Pile) - Backfill of Eroded Slope, Drainage Improvements and Erosion Control | 02/2017 | 4/2025 | 5/2025 | 12/2025 | 17 | 29 | 50 Years | 75 Years | No |
| Glenwood Dr | PM 2.58 | GLENWOOD DR PM 2.58 | Other | 35' long slipout along creek bank with undermning of roadway. Recommend cribwall and roadway reconstruction | 02/2023 | 05/2023 | 05/31/2023 | 08/2025 | 17 | 29 | 50 Years | 75 Years | No |
| Glenwood Dr | PM 2.60 | GLENWOOD DR PM 2.60 | Other | This project will include: Retaining Wall Failure Caused by Erosion Under Footing, Adjacent to Existing Retaining Walls (Crib) - Recommend Backfill Eroded Footing, Install Drainage | 02/2023 | 05/2023 | 05/31/2023 | 08/2025 | 17 | 29 | 50 Years | 75 Years | No |
| Glenwood Dr | PM 2.62 | GLENWOOD DR PM 2.62 | Other | 75' long slipout along creek bank with undermning of roadway. Recommend cribwall and roadway reconstruction | 02/2023 | 05/2023 | 05/31/2023 | 08/2025 | 17 | 29 | 50 Years | 75 Years | No |
| Glenwood Dr | PM 2.91 | GLENWOOD DR PM 2.91 | Other | Pavement Improvement (New).Right of Way Acquisition, Storm Drain and/or Culvert Rehab/Repair (Existing),Storm Drain/Culvert Installation (New) | 02/2023 | 05/2023 | 05/31/2023 | 08/2025 | 17 | 29 | 50 Years | 75 Years | No |
| Granite Creek Rd | PM 0.06 | Granite Creek Rd PM 0.06 | Other | This project will include: Cost Estimating, Document Preparation, Environmental Study/Documents, Preliminary Design | 02/2017 | 4/2025 | 5/2025 | 12/2025 | 17 | 29 | 50 Years | 75 Years | No |
| Granite Creek Rd | PM 0.47 | Granite Creek Rd PM 0.47 | Other | Slipout (50' L) - NB Shoulder Reconstruction, RSP and Overside Drain Replacement | 02/2017 | 4/2025 | 5/2025 | 12/2025 | 17 | 29 | 50 Years | 75 Years | No |
| Granite Creek Rd | PM 0.55 | Granite Creek Rd PM 0.55 | Other | This project will include: Cost Estimating, Document Preparation, Environmental Study/Documents, Preliminary Design | 02/2017 | 4/2025 | 5/2025 | 12/2025 | 17 | 29 | 50 Years | 75 Years | No |
| Granite Creek Rd | PM 2.10 | Granite Creek Rd PM 2.10 | Other | Slipout (3'-6" W x 10' L) - SB Traveled Way and Shoulder Reconstruction and Placement of RSP | 02/2017 | 4/2025 | 11/11/2023 | 12/2027 | 17 | 29 | 50 Years | 75 Years | No |
| Green Valley Rd | Holohan Rd to Mesa Verde Dr | Green Valley Rd Multi-Use Path | Other | Construct a multi-use path with improved bus stops and trash receptacles | 07/2022 | 07/2023 | 05/2024 | 07/2025 | 17 | 30 | 50 Years | 75 Years | Yes |
| Green Valley Rd | PM 1.85 | Green Valley Rd PM 1.85 | Other | Large Sinkhole Caused by Culvert Failure - 72" Culvert and Headwalls and Roadway Reconstruction | 02/2017 | 05/2022 | 05/2022 | 08/2025 | 17 | 29 | 50 Years | 75 Years | No |
| Green Valley Rd | PM 2.34 | Green Valley Rd PM 2.34 | Other | 25' long x 15' deep slipout. Edge of road undermned 1-2 feet. Recommend shoulder pile wall | 02/2023 | 05/2026 | 06/2026 | 12/2026 | 17 | 29 | 50 Years | 75 Years | No |
| Hazel Dell Rd | PM 2.00 | Hazel Dell Rd PM 2.00 | Other | Large Slipout/ landslide 85' long x 10' deep, slip potential - Retaining Wall Installation | 02/2017 | 05/2022 | 05/2022 | 08/2025 | 17 | 29 | 50 Years | 75 Years | No |
| Hazel Dell Rd | PM 2.08 | Hazel Dell Rd PM 2.08 | Other | Large Slipout, Roadway Reconstruction, Drainage Improvements and Retaining Wall (TBD) Installation | 02/2017 | 05/2022 | 05/2022 | 08/2025 | 17 | 29 | 50 Years | 75 Years | No |
| Hazel Dell Rd | PM 2.13 | Hazel Dell Rd PM 2.13 | Other | Slipout - 30' wide by 10' deep, Shoulder Reconstruction and Retaining Wall (Soldier Pile) Installation | 02/2017 | 05/2022 | 05/2022 | 08/2025 | 17 | 29 | 50 Years | 75 Years | No |
| Hazel Dell Rd | PM 2.16 | Hazel Dell Rd PM 2.16 | Other | Settling Roadway 85' long, possible cross culvert damage, Culvert Replacement, Roadway and Shoulder Reconstruction and Retaining Wall (Soldier Pile) Installation | 02/2017 | 05/2022 | 05/2022 | 08/2025 | 17 | 29 | 50 Years | 75 Years | No |
| Hazel Dell Rd | PM 2.21 | Hazel Dell Rd PM 2.21 | Other | Failing Crib Wall - 50' long x 12' tall, Shoulder Reconstruction and Retaining Wall Structure | 02/2017 | 05/2022 | 05/2022 | 08/2025 | 17 | 29 | 50 Years | 75 Years | No |
| Hazel Dell Rd | PM 2.35 | HAZEL DELL PM 2.35 | Other | 50' long slipout half way into roadway. Soil nail wall to stabilize and then MSE wall. | 02/2023 | 05/2025 | 05/31/2023 | 12/2025 | 17 | 29 | 50 Years | 75 Years | No |
| Hazel Dell Rd | PM 2.37 | Hazel Dell Rd PM 2.37 | Other | Slipout with Embankment Settlement, Shoulder Reconstruction and Retaining Wall | 02/2017 | 05/2021 | 05/2022 | 08/2025 | 17 | 29 | 50 Years | 75 Years | No |
| Hazel Dell Rd | PM 2.57 | HAZEL DELL RD PM 2.57 | Other | Slipout 50' long, Soldier pile repair with roadway reconstruction | 02/2023 | 05/2026 | 06/2026 | 12/2026 | 17 | 29 | 50 Years | 75 Years | No |
| Hazel Dell Rd | PM 2.58 | Hazel Dell Rd PM 2.58 | Other | Failed Crib Wall, Reconstruct Damaged Shoulder and Roadway, Retaining Wall (Soldier Pile) Installation | 02/2017 | 05/2021 | 05/2022 | 08/2025 | 17 | 29 | 50 Years | 75 Years | No |
| Hazel Dell Rd | PM 2.61 | HAZEL DELL RD PM 2.61 | Other | This project will include: Slipout 24' long. Recommend soldier pile wall | 02/2023 | 04/2023 | 6/15/2023 | 12/2027 | 17 | 29 | 50 Years | 75 Years | No |
| Hazel Dell Rd | PM 2.63 | HAZEL DELL RD PM 2.63 | Other | 65' long slipout half way into roadway. Soldier pile wall repair | 02/2023 | 05/2023 | 5/17/2023 | 12/2027 | 17 | 29 | 50 Years | 75 Years | No |
| Hazel Dell Rd | PM 3.43 | Hazel Dell Rd PM 3.43 | Other | This project will include repair of a Road edge slipout 6' x 6' | 03/2024 | 05/2027 | 06/2027 | 12/2027 | 17 | 29 | 50 Years | 75 Years | No |
| Highland Way | PM 0.70 | Highland Way PM 0.70 | Other | 30' long by 5' tall shoulder slipout 6' into roadway, Caused by fallen tree. RSP repair with roadway reconstruction | 02/2023 | 05/2026 | 06/2026 | 12/2026 | 17 | 29 | 50 Years | 75 Years | No |
| Highland Way | PM 2.40 | Highland Way PM 2.40 | Other | Road sinking and shifting 50x10. Recommend reconstruction roadway and geogrid slope reinforcement | 02/2023 | 05/2026 | 06/2026 | 12/2026 | 17 | 29 | 50 Years | 75 Years | No |
| Highland Way | PM 3.73 | HIGHLAND WAY PM 3.73 | Other | Roadway damage on both sides of recently constructed soldier pile wall. Reccoment extending soldier pile walls with roadway reconstruction | 02/2023 | 04/2023 | 8/3/2023 | 12/2027 | 17 | 29 | 50 Years | 75 Years | No |
| Highland Way | PM 3.91 | HIGHLAND WAY PM 3.91 | Other | This project will include: Slipout (10+/-' W x 25' L) - Recommend SB (Outboard) Traveled Way and Shoulder Reconstruction, Drainage Improvements and Retaining Wall (Soldier Pile) Installation | 02/2023 | 04/2023 | 03/31/2023 | 08/2025 | 17 | 29 | 50 Years | 75 Years | No |
| Highland Way | PM 4.55 | HIGHLAND WAY PM 4.55 | Other | 50' long slipout taking out most of roadway near culvert. MSE wall repair | 02/2023 | 05/2023 | 5/10/2023 | 12/2027 | 17 | 29 | 50 Years | 75 Years | No |
| Holohan Rd | Green Valley Rd to Hwy 152 | Holohan Road Multi-Use Path | Other | Construct a multi-use path | 06/2023 | 06/2025 | 08/2025 | 07/2026 | 17 | 30 | 50 Years | 75 Years | No |
| Holohan Rd and College Rd | Hwy 152 | Holohan Road and College Road at Hwy 152 | Traffic Control Devices | Traffic signal, sidewalk and drainage improvements, striping | 02/2017 | 05/2022 | 05/2022 | 12/2025 | 17 | 30 | 50 Years | 75 Years | No |
| Hopkins Gulch Rd | #4 | Hopkins Gulch Rd #4 | Other | This project will include: Document Preparation, Environmental Study/Documents, Feasibility Study, Preliminary Design, Right of Way | 02/2023 | 05/2023 | 05/31/2023 | 08/2025 | 17 | 29 | 50 Years | 75 Years | No |

Exhibit A
RMRA Project List for 2025/2026 Fiscal Year

| Project Road | Project Location | Project Title | Project Type | Project Description | Pre-Construction Estimated Start | Pre-Construction Estimated Completion | Construction Estimated Start | Construction Estimated Completion | State Senate | State Assembly | Estimated Minimum Useful Life | Estimated Maximum Useful Life | Additional Project Elements |
|-------------------|---------------------|---------------------------------------|-----------------------------------|---|----------------------------------|---------------------------------------|------------------------------|-----------------------------------|--------------|----------------|-------------------------------|-------------------------------|-----------------------------|
| Ice Cream Grade | PM 1.24 | Ice Cream Grade Rd PM 1.24 | Other | Road Edge failure above culvert wall above wingwall is failing. Construct new headwall | 02/2023 | 05/2026 | 06/2026 | 12/2026 | 17 | 29 | 50 Years | 75 Years | No |
| Ice Cream Grade | PM 1.36 | Ice Cream Grade Rd PM 1.36 | Other | Slipout - 105'L x 8'D - install soldier pile wall | 02/2017 | 04/2022 | 06/2022 | 08/2025 | 17 | 29 | 50 Years | 75 Years | No |
| Ice Cream Grade | PM 1.55 | Ice Cream Grade Rd PM 1.55 | Road Maintenance & Rehabilitation | 42' L slipout, install wall, pavement repair, erosion control | 02/2017 | 04/2022 | 06/2022 | 08/2025 | 17 | 29 | 50 Years | 75 Years | No |
| Ice Cream Grade | PM 1.60 | Ice Cream Grade Rd PM 1.60 | Other | Road/Embankment Settling (12' W x 100' L) - Recommend EB Traveled Way and Shoulder Reconstruction, Drainage Improvements and Retaining Wall (Soldier Pile) Installation | 02/2017 | 04/2022 | 06/2022 | 08/2025 | 17 | 29 | 50 Years | 75 Years | No |
| Jamison Creek Rd | PM 1.61 | Jamison Creek Road PM 1.61 | Other | Slipout - 25'L x 10'D - Roadway and Shoulder Reconstruction and Installation of Soldier Pile Wall | 02/2017 | 4/2024 | 5/2024 | 08/2025 | 17 | 29 | 50 Years | 75 Years | No |
| Jarvis Rd | PM 0.64 | Jarvis Rd PM 0.64 | Other | Slipout (6' W x 20+/-') - NB (Outboard) Traveled Way and Shoulder Reconstruction, Earth backfill and Downdrain | 02/2017 | 4/2025 | 06/2026 | 12/2026 | 17 | 29 | 50 Years | 75 Years | No |
| Jarvis Rd | PM 0.68 | Jarvis Rd PM 0.68 | Other | Culvert Failure & Roadway/Embankment Settling - Roadway Reconstruction and Drainage Improvements including 18" Culvert and Headwalls - SB Shoulder Reconstruction, Drainage Improvements and Retaining Wall (Soldier Pile) Installation, | 02/2017 | 4/2025 | 06/2026 | 12/2026 | 17 | 29 | 50 Years | 75 Years | No |
| Jarvis Rd | PM 1.02, 1.04, 1.07 | Jarvis Rd PM 1.02, 1.04, 1.07 | Other | PM 1.02 - Slipout (20+1/2' W x 60' L) - SB Shoulder Reconstruction, Drainage Improvements and Retaining Wall (Soldier Pile) Installation, PM 1.04 - Slipout (6' W x 40' L) - SB (Outboard) Traveled Way and Shoulder Reconstruction, Drainage Improvements and Retaining Wall (Crib) Installation | 02/2017 | 4/2025 | 06/2026 | 12/2026 | 17 | 29 | 50 Years | 75 Years | No |
| Jarvis Rd | PM 1.66 | Jarvis Rd PM 1.66 | Other | Culvert Failure & Roadway/Embankment Settling - Roadway Reconstruction and Drainage Improvements including 16" Culvert and Headwalls | 02/2017 | 4/2025 | 5/2025 | 12/2025 | 17 | 29 | 50 Years | 75 Years | No |
| Kings Creek Rd | PM 1.65 | Kings Creek Rd PM 1.65 | Other | Slipout and Damaged Downdrain - Installation of Gabion Baskets or RSP, Backfill and Reinstall Culvert | 02/2017 | 4/2025 | 5/2025 | 12/2025 | 17 | 29 | 50 Years | 75 Years | No |
| Kings Creek Rd | PM 3.03 | Kings Creek Rd PM 3.03 | Other | Slipout (40' L) and Landslide - Roadway Reconstruction, Drainage Improvements and Retaining Wall (Soldier Pile) Installation | 02/2017 | 4/2025 | 5/2025 | 12/2025 | 17 | 29 | 50 Years | 75 Years | No |
| Kings Creek Rd | PM 3.16 | Kings Creek Rd PM 3.16 | Other | Slipout and Roadway/Embankment Settling - Roadway Reconstruction, Drainage Improvements, and Retaining Wall (Stitch Pile) Installation | 02/2017 | 4/2025 | 5/2025 | 12/2025 | 17 | 29 | 50 Years | 75 Years | No |
| Lakeview Dr | PM 0.42 | LAKEVIEW DR PM 0.42 | Other | Landscape Safety Installation (New), Pavement Rehab/Repair (Existing) 20' long shoulder slipout due to fallen tree. Recommend soldier pile wall and reconstruct portion of roadway. | 02/2023 | 05/2023 | 05/31/2023 | 08/2025 | 17 | 29 | 50 Years | 75 Years | No |
| Lakeview Dr RI | PM 0.52 | LAKEVIEW DR PM 0.52 | Other | This project will include: Storm Drain/Culvert Installation (New) | 02/2023 | 05/2023 | 05/31/2023 | 08/2025 | 17 | 29 | 50 Years | 75 Years | No |
| Little Basin Rd | PM 0.64 | Little Basin Rd PM 0.64 | Other | Slipout (35' L) - EB (Outboard) Roadway Reconstruction, Drainage Improvements and Retaining Wall (Soldier Pile) Installation | 02/2017 | 6/2024 | 7/2024 | 08/2025 | 17 | 29 | 50 Years | 75 Years | No |
| Little Basin Rd | PM 0.85 | Little Basin Rd PM 0.85 | Other | Slipout (80' L) - SB (Outboard) Traveled Way and Shoulder Reconstruction, Drainage Improvements and Retaining Wall (Soldier Pile) Installation | 02/2017 | 6/2024 | 7/2024 | 08/2025 | 17 | 29 | 50 Years | 75 Years | No |
| Little Basin Rd | PM 1.50 | Little Basin Rd PM 1.50 | Other | 30' long slipout along shoulder, recommend soldier pile wall | 02/2023 | 05/2026 | 06/2026 | 12/2026 | 17 | 29 | 50 Years | 75 Years | No |
| Lockhart Gulch Rd | Nelson Rd | Lockhart Gulch at Nelson Rd - Slipout | Other | 20' long shoulder slipout. Cribwall repair | 03/2023 | 06/2023 | 03/31/2023 | 08/2025 | 17 | 29 | 50 Years | 75 Years | No |
| Lockhart Gulch Rd | PM 0.24 | Lockhart Gulch Rd PM 0.24 | Other | Slipout (55'L) - NB Shoulder Reconstruction, Drainage Improvements, and Retaining Wall (Crib) Installation | 02/2017 | 5/2023 | 5/2023 | 08/2025 | 17 | 29 | 50 Years | 75 Years | No |
| Lockhart Gulch Rd | PM 0.35 | LOCKHART GULCH PM 0.35 | Other | 60' long by 10' tall shoulder slipout. Cribwall repair recommended. | 02/2023 | 05/2025 | 5/31/2025 | 12/2025 | 17 | 29 | 50 Years | 75 Years | No |
| Lockhart Gulch Rd | PM 1.68 | LOCKHART GULCH PM 1.68 | Other | This project will include: Landscape Safety Installation (New), Paving and/or Striping Installation (New Safety) 50' slipout, half of road gone. Recommend soldier pile wall with roadway reconstruction. | 02/2023 | 05/2023 | 3/16/2023 | 12/2027 | 17 | 29 | 50 Years | 75 Years | No |
| Lodge Rd | PM 1.07 | Lodge Road PM 1.07 | Other | 60' long slipout. Only 5' left of road. Recommend shoulder pile or soil nail wall | 02/2023 | 05/2026 | 06/2026 | 12/2026 | 17 | 29 | 50 Years | 75 Years | No |
| Loma Prieta Av | PM 2.82 | Loma Prieta Av PM 2.82 | Other | This project will include: Storm Drain and/or Culvert Rehab/Repair (Existing) Slipout (20'L) - Recommend SB Shoulder Reconstruction, Drainage Improvements, and Retaining Wall (Soldier Pile) Installation | 02/2017 | 05/2025 | 05/2025 | 12/2025 | 17 | 29 | 50 Years | 75 Years | No |
| Loma Prieta Wy | PM 3.33 | Loma Prieta Wy PM 3.33 | Other | This project will include: Storm Drain and/or Culvert Rehab/Repair (Existing) Slipout (60' L) - Recommend EB Traveled Way and Shoulder Reconstruction, Drainage Improvements and Retaining Wall (Soldier Pile) Installation | 02/2017 | 05/2025 | 05/2025 | 12/2025 | 17 | 29 | 50 Years | 75 Years | No |
| Lompico Rd | PM 0.22 | Lompico Rd PM 0.22 | Other | This project will include: Pavement Rehab/Repair (Existing) Slipout (40' W x 100' L) - Recommend SB Traveled Way and Shoulder Reconstruction and Retaining Wall (Soldier Pile) Installation | 02/2017 | 4/2025 | 5/2025 | 12/2027 | 17 | 29 | 50 Years | 75 Years | No |
| Lompico Rd | PM 0.70 | Lompico Rd PM 0.70 | Other | This project will include: Cost Estimating, Document Preparation, Environmental Study/Documents, Preliminary Design | 02/2017 | 4/2025 | 5/2027 | 12/2027 | 17 | 29 | 50 Years | 75 Years | No |
| Lompico Rd | PM 0.80 | Lompico Rd PM 0.80 | Other | 30' long slipout due to tree falling on shoulder of road. RSP repair | 02/2017 | 05/2025 | 05/2025 | 12/2025 | 17 | 29 | 50 Years | 75 Years | No |
| Lompico Rd | PM 1.09 | LOMPICO RD PM 1.09 | Other | This project will include: Landscape Safety Installation (New) | 02/2023 | 05/2025 | 5/31/2025 | 12/2025 | 17 | 29 | 50 Years | 75 Years | No |
| Lompico Rd | PM 1.22 | Lompico Rd PM 1.22 | Other | Slipout (45' L) - NB Shoulder Reconstruction, Drainage Improvements, RSP and Retaining Wall (Crib) Installation | 02/2017 | 4/2025 | 5/2025 | 12/2025 | 17 | 29 | 50 Years | 75 Years | No |
| Lompico Rd | PM 2.38 | Lompico Rd PM 2.38 | Other | Slipout (10' W x 25' L) - NB Travelled Way and Shoulder Reconstruction and Installation of Retaining Wall (Crib) | 02/2017 | 4/2025 | 5/2026 | 12/2026 | 17 | 29 | 50 Years | 75 Years | No |
| Lompico Rd | PM 1.85 | LOMPICO RD PM 1.85 | Other | This project will include: Landscape Safety Installation (New) 80' x 20' Slipout. Recommend rock slope protection backfill to stabilize slope. | 01/2023 | 02/2023 | 02/28/2023 | 08/2025 | 17 | 29 | 50 Years | 75 Years | No |
| Lompico Rd | West Dr | LOMPICO RD @ WEST DR | Other | This project will include: Landscape Safety Installation (New) | 01/2023 | 02/2023 | 02/28/2023 | 08/2025 | 17 | 29 | 50 Years | 75 Years | No |
| Love Creek Rd | PM 0.35 | Love Creek Rd PM 0.35 | Other | This project will include: Landscape Safety Rehab/Repair (Existing), Paving and/or Striping Rehab/Repair (Existing Safety) 35' long slipout 4' into roadway. Recommend cribwall repair | 02/2017 | 4/2025 | 5/2025 | 12/2027 | 17 | 29 | 50 Years | 75 Years | No |
| Lower Highland Wy | PM 0.34 | Lower Highland Wy PM 0.34 | Other | This project will include: Slipout (18' W x 65'L) - Recommend Traveled Way and Shoulder Reconstruction, RSP, and Retaining Wall (Soldier Pile) Installation | 02/2017 | 4/2025 | 5/2025 | 12/2027 | 17 | 29 | 50 Years | 75 Years | No |
| Main St | BATES CREEK | MAIN ST @ BATES CREEK | Other | Large culvert failure with road washout. Construct reinforced concrete box culvert allowing fish passage. | 03/2023 | 06/2023 | 03/31/2023 | 12/2027 | 17 | 29 | 50 Years | 75 Years | No |

Exhibit A
RMRA Project List for 2025/2026 Fiscal Year

| Project Road | Project Location | Project Title | Project Type | Project Description | Pre-Construction Estimated Start | Pre-Construction Estimated Completion | Construction Estimated Start | Construction Estimated Completion | State Senate | State Assembly | Estimated Minimum Useful Life | Estimated Maximum Useful Life | Additional Project Elements |
|--------------------|------------------|--------------------------------|--------------|---|----------------------------------|---------------------------------------|------------------------------|-----------------------------------|--------------|----------------|-------------------------------|-------------------------------|-----------------------------|
| Miller Cut-off Rd | PM 0.47 | Miller Cut-off Rd PM 0.47 | Other | Repair combined with Miller Cutoff 0.49. Slipout (15' W x 85'L) Adjacent to Existing Crib Wall (Installed 2016) - NB (Outboard) Traveled Way and Shoulder Reconstruction, Drainage Improvements and Retaining Wall (Soldier Pile) Installation | 02/2017 | 4/2025 | 5/2025 | 12/2025 | 17 | 29 | 50 Years | 75 Years | No |
| Miller Cut-off Rd | PM 0.49 | Miller Cut-off Rd PM 0.49 | Other | Slipout (15' W x 85'L) Adjacent to Existing Crib Wall (Installed 2016) - NB (Outboard) Traveled Way and Shoulder Reconstruction, Drainage Improvements and Retaining Wall (Soldier Pile) Installation | 02/2017 | 4/2025 | 5/2025 | 12/2025 | 17 | 29 | 50 Years | 75 Years | No |
| Morrell Rd | PM 0.50 | Morrell Rd PM 0.50 | Other | This project will include: Cost Estimating, Document Preparation, Environmental Study/Documents, Preliminary Design, Right of Way Slipout and Culvert Failure-Recommend Roadway Reconstruction, 18" and 24" Culvert Replacement and Retaining Wall (Soldier Pile) Installation | 03/2025 | 05/2026 | 4/30/2027 | 12/2027 | 17 | 29 | 50 Years | 75 Years | No |
| Mt Bache Rd | PM 0.50 | MT BACHE RD PM 0.50 | Other | This project will include: Storm Drain/Culvert Installation (New) | 02/2023 | 04/2023 | 04/30/2023 | 08/2025 | 17 | 29 | 50 Years | 75 Years | No |
| Mt Charlie Rd | PM 0.26 | Mt Charlie Road PM 1.26 | Other | This project will include: Pavement Rehab/Repair (Existing), Storm Drain and/or Culvert Rehab/Repair (Existing) Pier & Lagging Wall w/ tiebacks, guard rail, ae dike, drainage facilities, pavement repair, erosion control | 02/2023 | 04/2023 | 04/30/2023 | 08/2025 | 17 | 29 | 50 Years | 75 Years | No |
| Mt Charlie Rd | PM 1.66 | Mt Charlie Road PM 1.66 | Other | 100' roadway slipout with road closure. Recommend soldier pile wall with road reconstruction | 02/2023 | 05/2025 | 06/2025 | 12/2025 | 17 | 29 | 50 Years | 75 Years | No |
| Mt Charlie Rd | PM 1.94 | Mt Charlie Road PM 1.94 | Other | 50' long slipout near culvert. Soldier pile wall repair | 02/2023 | 05/2025 | 06/2025 | 12/2025 | 17 | 29 | 50 Years | 75 Years | No |
| Mt Charlie Rd | PM 4.48 | Mt Charlie Road PM 4.48 | Other | This project will include repair of a Road edge slipout 40' long | 03/2024 | 05/2027 | 06/2027 | 12/2027 | 17 | 29 | 50 Years | 75 Years | No |
| Mountain View Rd | PM 0.25 | Mountain View Rd PM 0.25 | Other | This project will include repair of lost road shoulder | 03/2024 | 05/2027 | 06/2027 | 12/2027 | 17 | 29 | 50 Years | 75 Years | No |
| Nelson Rd | PM 0.43 | Nelson Rd PM 0.43 | Other | 3 Slipouts (Varying 30 to 50' L) - NB Traveled Way and Shoulder Reconstruction, Drainage Improvements and Retaining Wall (Soldier Pile) Installation | 02/2017 | 4/2024 | 5/2024 | 08/2025 | 17 | 29 | 50 Years | 75 Years | No |
| Nelson Rd | PM 0.44 | Nelson Rd PM 0.44 | Other | Road washout due to clogged culvert/flooding. Place new culvert, place headwalls, and reconstruct roadway | 02/2017 | 4/2025 | 5/2026 | 12/2026 | 17 | 29 | 50 Years | 75 Years | No |
| Mountain View Rd | PM 1.88 | North Rodeo Gulch Rd PM 1.88 | Other | This project will include repair of a road edge following tree fall and uprooting | 03/2024 | 05/2027 | 06/2027 | 12/2027 | 17 | 29 | 50 Years | 75 Years | No |
| Mountain View Rd | PM 2.58 | North Rodeo Gulch Rd PM 2.58 | Other | This project will include repair of a road edge following tree fall and uprooting | 03/2024 | 05/2027 | 06/2027 | 12/2027 | 17 | 29 | 50 Years | 75 Years | No |
| Mountain View Rd | PM 2.70 | North Rodeo Gulch Rd PM 2.70 | Other | This project will include repair of 3 sections of road edge damage: 15x4, 33x4, 2x2 feet | 03/2024 | 05/2027 | 06/2027 | 12/2027 | 17 | 29 | 50 Years | 75 Years | No |
| North Rodeo Gulch | PM 3.77 | North Rodeo Gulch Road PM 3.77 | Other | 50' long slipout into roadway. Lane closed. Soldier pile wall repair | 02/2023 | 05/2025 | 06/2025 | 12/2025 | 17 | 29 | 50 Years | 75 Years | No |
| North Rodeo Gulch | PM 3.82 | North Rodeo Gulch PM 3.82 | Other | Slipout (6' W x 50' L) - SB Traveled Way and Shoulder Reconstruction, Drainage Improvements and Retaining Wall (Soldier Pile) Installation | 02/2017 | 4/2025 | 5/2025 | 12/2025 | 17 | 29 | 50 Years | 75 Years | No |
| Old Bear Creek Rd | PM 0.01 | Old Bear Creek Rd PM 0.01 | Other | This project will include: Slipout (20' W x 36' L) - Recommend WB Traveled Way and Shoulder Reconstruction, Drainage Improvements and Retaining Wall (Soldier Pile) Installation | 2/2017 | 12/2020 | 6/2021 | 12/2027 | 17 | 29 | 50 Years | 75 Years | No |
| Old Santa Cruz Hwy | PM 1.01 | Old Santa Cruz Hwy PM 1.01 | Other | Slipout (50'L) - NB/EB (Outboard) Traveled Way and Shoulder Reconstruction, Drainage Improvements and Retaining Wall (Soldier Pile) Installation | 02/2017 | 4/2025 | 5/2025 | 12/2025 | 17 | 29 | 50 Years | 75 Years | No |
| Old Santa Cruz Hwy | PM 1.06 | Old Santa Cruz Hwy PM 1.06 | Other | Slipout - NB/EB Traveled Way and Shoulder Reconstruction and Retaining Wall (Soldier Pile) Installation | 02/2017 | 4/2025 | 5/2025 | 12/2025 | 17 | 29 | 50 Years | 75 Years | No |
| Old Santa Cruz Hwy | PM 1.20 | Old Santa Cruz Hwy PM 1.20 | Other | This project will include: Storm Drain and/or Culvert Rehab/Repair (Existing) Slipout (10' W x 50' L) - Recommend NB/EB Traveled Way, Drainage Improvements and Shoulder Reconstruction and Retaining Wall (Crib) Installation | 02/2017 | 4/2025 | 5/2025 | 12/2025 | 17 | 29 | 50 Years | 75 Years | No |
| Old Santa Cruz Hwy | PM 1.36 | Old Santa Cruz Hwy PM 1.36 | Other | This project will include: Storm Drain and/or Culvert Rehab/Repair (Existing) Slipout (12' W x 90' L) - Recommend NB/EB (Outboard) Traveled Way and Shoulder Reconstruction and Retaining Wall (Soldier Pile) Installation | 02/2017 | 4/2025 | 5/2025 | 12/2025 | 17 | 29 | 50 Years | 75 Years | No |
| Paulsen Rd | PM 0.43 | Paulsen Rd PM 0.43 | Other | This project will include: Storm Drain and/or Culvert Rehab/Repair (Existing) | 2/2017 | 12/2020 | 6/2021 | 12/2027 | 17 | 29 | 50 Years | 75 Years | No |
| Prescott Rd | PM 0.52 | Prescott Rd PM 0.52 | Other | Slipout - NB Shoulder Reconstruction, Drainage Improvements and Retaining Wall (Crib) Installation | 02/2017 | 4/2025 | 5/2026 | 12/2026 | 17 | 29 | 50 Years | 75 Years | No |
| Redwood Dr | Oak Dr | REDWOOD DR @ OAK DR | Other | This project will include: Landscape Safety Installation (New) 40' long slipout on south side of culvert and failed section of cribwall undermining road on north side. Recommend rock slope protection backfill on one side and soil nail wall on other. | 01/2023 | 02/2023 | 02/28/2023 | 12/2027 | 17 | 29 | 50 Years | 75 Years | No |
| Redwood Dr | PM 0.19 | REDWOOD DR PM 0.19 | Other | This project will include: Landscape Safety Rehab/Repair (Existing).Pavement Improvement (New).Storm Drain/Culvert Installation (New) Culvert failure, undermining road. Recommend culvert replacement and adding headwalls | 01/2023 | 02/2023 | 06/30/2023 | 12/2027 | 17 | 29 | 50 Years | 75 Years | No |
| Redwood Lodge Rd | PM 1.80 | Redwood Lodge Rd PM 1.80 | Other | Culvert Failure and temp repair failure. Must be replaced with a bridge. Embankment reconstruction, excavation and backfill, concrete headwall, 120" culvert, erosion control and revegetation. | 02/2017 | 3/2027 | 5/2027 | 12/2027 | 17 | 29 | 50 Years | 75 Years | No |
| Redwood Lodge Rd | PM 2.02 | Redwood Lodge Rd PM 2.02 | Other | This project will include: Landscape Safety Rehab/Repair (Existing), Storm Drain and/or Culvert Rehab/Repair (Existing) Preparation of design and environmental documents for large Slipout (30' W x 120' L) and Landslide - Recommend Roadway Reconstruction and Retaining Wall (Stitch Pile) Installation | 03/2023 | 3/2027 | 5/2027 | 12/2027 | 17 | 29 | 50 Years | 75 Years | No |
| Redwood Lodge Rd | PM 2.25 | Redwood Lodge Rd PM 2.25 | Other | Shoulder damage, 30' long, 2' into roadway. Recommend shoulder pile wall | 02/2023 | 05/2026 | 06/2026 | 12/2026 | 17 | 29 | 50 Years | 75 Years | No |
| Redwood Rd | PM 0.05 | Redwood Rd PM 0.05 | Other | 30' long slipout halfway into road. Recommend shoulder pile wall with roadway reconstruction | 02/2023 | 05/2025 | 06/2025 | 12/2025 | 17 | 29 | 50 Years | 75 Years | No |
| Redwood Rd | PM 0.06 | Redwood Rd PM 0.06 | Other | This project will include: Cost Estimating, Document Preparation, Environmental Study/Documents, Preliminary Design | 02/2023 | 05/2025 | 06/2025 | 12/2025 | 17 | 29 | 50 Years | 75 Years | No |
| Redwood Rd | PM 0.15 | Redwood Rd PM 0.15 | Other | Slipout (50' L) - SB (Outboard) Traveled Way and Shoulder Reconstruction, Drainage Improvements and Retaining Wall (Soldier Pile) Installation | 02/2017 | 5/2024 | 5/2024 | 08/2025 | 17 | 29 | 50 Years | 75 Years | No |

Exhibit A
RMRA Project List for 2025/2026 Fiscal Year

| Project Road | Project Location | Project Title | Project Type | Project Description | Pre-Construction Estimated Start | Pre-Construction Estimated Completion | Construction Estimated Start | Construction Estimated Completion | State Senate | State Assembly | Estimated Minimum Useful Life | Estimated Maximum Useful Life | Additional Project Elements |
|--------------------|-------------------------------------|--|--|---|----------------------------------|---------------------------------------|------------------------------|-----------------------------------|--------------|----------------|-------------------------------|-------------------------------|-----------------------------|
| Redwood Rd | PM 0.23 | Redwood Rd PM 0.23 | Other | This project will include: Landscape Safety Rehab/Repair (Existing), Pavement Rehab/Repair (Existing), Storm Drain and/or Culvert Rehab/Repair (Existing) Slipout (18' W x 35' L) - Recommend NB (Outboard) Shoulder Reconstruction, Drainage Improvements and Retaining Wall (Crib) Installation | 02/2017 | 5/2024 | 5/2024 | 08/2025 | 17 | 29 | 50 Years | 75 Years | No |
| Redwood Rd | PM 0.29, 0.31, 0.33 | Redwood Rd PM 0.29, 0.31, 0.33 | Other | PM 0.29 Roadway/Embankment Settling (120' L) Near Existing Retaining Wall - NB (Outboard) Shoulder Reconstruction and Retaining Wall (Soldier Pile) Installation, PM 0.31 Slipout (40' L) - NB (Outboard) Traveled Way and Shoulder Reconstruction, 18" Culvert, RSP and Retaining Wall (Soldier Pile) Installation, PM 0.33 Culvert Failure & Slipout (30' L) - NB (Outboard) Shoulder Reconstruction, Drainage Improvements including 18" Culvert | 02/2017 | 05/2022 | 05/2022 | 08/2025 | 17 | 29 | 50 Years | 75 Years | No |
| Redwood Rd | PM 0.38, 0.40 | Redwood Rd PM 0.38, 0.40 | Other | PM 0.38 Slipout (50' L) - NB (Outboard) Traveled Way and Shoulder Reconstruction, Drainage Improvements and Retaining Wall (Soldier Pile) Installation, PM 0.40 ULTRABLOCK Retaining Wall Failure - NB (Outboard) Shoulder Reconstruction, Drainage Improvements and Retaining Wall (Soldier Pile) | 02/2017 | 4/2025 | 5/2026 | 12/2026 | 17 | 29 | 50 Years | 75 Years | No |
| Redwood Rd | PM 0.97 | Redwood Rd PM 0.97 | Other | 10' long by 7' tall shoulder slipout encroaching a foot into roadway. Recommend shoulder pile wall | 02/2023 | 05/2026 | 06/2026 | 12/2026 | 17 | 29 | 50 Years | 75 Years | No |
| Redwood Rd | PM 1.67 | Redwood Road PM 1.67 | Other | Damaged culvert and rowad shoulder from storms. Culvert replacement with headwalls | 02/2023 | 05/2025 | 06/2025 | 12/2025 | 17 | 29 | 50 Years | 75 Years | No |
| Rider Rd | PM 0.38 | Rider Road PM 0.38 | Other | 35' long shoulder slipout above creek. RSP repair | 02/2023 | 04/2023 | 06/30/2023 | 08/2025 | 17 | 29 | 50 Years | 75 Years | No |
| Rider Rd | PM 0.40 | RIDER RD PM 0.40 | Other | This project will include: Landscape Safety Rehab/Repair (Existing) Slipout along edge of road with undermining of roadway. Recommend rock slope protection backfill to stabilize slope. | 01/2023 | 02/2023 | 02/28/2023 | 08/2025 | 17 | 29 | 50 Years | 75 Years | No |
| Rider Rd | PM 0.80 | Rider Road PM 0.80 | Other | 80' L slipout. Installing Soldier Pile Wall, Pavement and Shoulder Reconstruction | 02/2017 | 4/2025 | 5/2025 | 12/2025 | 17 | 29 | 50 Years | 75 Years | No |
| Rider Rd | PM 0.85 | Rider Rd PM 0.85 | Other | 30' slipout along shoulder - RSP repair | 02/2023 | 05/2026 | 06/2026 | 12/2026 | 17 | 29 | 50 Years | 75 Years | No |
| Rider Rd | PM 1.38 | Rider Rd PM 1.38 | Other | slipout along shoulder, recommend RSP repair | 02/2023 | 05/2026 | 06/2026 | 12/2026 | 17 | 29 | 50 Years | 75 Years | No |
| San Andreas Rd | PM 1.24 | SAN ANDREAS RD PM 1.24 | Other | This project will include: Landscape Safety Installation (New), Pavement Improvement (New), Storm Drain/Culvert Installation (New) Slipout (20' W x 40' L) - Recommend SB Shoulder Reconstruction, Drainage Improvements and Retaining Wall (Soldier Pile) Installation | 02/2017 | 05/2025 | 05/2025 | 12/2025 | 17 | 29 | 50 Years | 75 Years | No |
| San Andreas Rd | PM 2.14 | SAN ANDREAS RD PM 2.14 | Other | Failed 36-inch culvert due to storm flows. Replace culvert and catch basin | 02/2017 | 05/2025 | 05/2025 | 12/2025 | 17 | 29 | 50 Years | 75 Years | No |
| San Lorenzo Way | San Lorenzo River | San Lorenzo Way Bridge | Bridge Structure Repair/Rehab (Existing) | Replace Existing Bridge | 02/2017 | 4/2025 | 5/2025 | 12/2025 | 17 | 29 | 50 Years | 75 Years | No |
| Schullies Rd | PM 0.40 | Schullies Rd PM 0.40 | Other | This project will include repair of a Road edge slipout 80' | 01/2021 | 3/2026 | 5/2027 | 12/2027 | 17 | 29 | 50 Years | 75 Years | No |
| Schullies Rd | PM 1.14 | Schullies Rd PM 1.14 | Other | This project will include: Cost Estimating, Document Preparation, Environmental Study/Documents, Preliminary Design | 2/2017 | 3/2025 | 6/2025 | 12/2025 | 17 | 29 | 50 Years | 75 Years | No |
| Smith Grade Rd | PM 0.43 | Smith Grade Rd PM 0.43 | Other | This project will include: Pavement Rehab/Repair (Existing) slipout/settlement pavement separation | 02/2017 | 04/2022 | 01/2022 | 08/2025 | 17 | 29 | 50 Years | 75 Years | No |
| Smith Grade Rd | PM 0.52 | Smith Grade Rd PM 0.52 | Other | This project will include: Storm Drain and/or Culvert Rehab/Repair (Existing) | 02/2017 | 04/2022 | 06/2022 | 08/2025 | 17 | 29 | 50 Years | 75 Years | No |
| Smith Grade Rd | PM 1.38 | Smith Grade PM 1.38 | Other | Road slump. Slurry and earth backfill repair | 02/2017 | 04/2022 | 06/2022 | 08/2025 | 17 | 29 | 50 Years | 75 Years | No |
| Smith Grade Rd | PM 1.90 | Smith Grade Rd PM 1.90 | Other | This project will include: Pavement Rehab/Repair (Existing) 3' diameter sinkhole | 02/2017 | 04/2022 | 06/2022 | 08/2025 | 17 | 29 | 50 Years | 75 Years | No |
| Smith Grade Rd | PM 2.83 | Smith Grade Rd PM 2.83 | Other | This project will include: Storm Drain and/or Culvert Rehab/Repair (Existing) | 02/2017 | 04/2022 | 06/2022 | 08/2025 | 17 | 29 | 50 Years | 75 Years | No |
| Smith Grade Rd | PM 4.06 | Smith Grade Rd PM 4.06 | Other | Slipout (25' W x 12' L) - EB (Outboard) Shoulder Reconstruction, Drainage Improvements and Retaining Wall (Soldier Pile) Installation | 02/2017 | 4/2025 | 5/2025 | 12/2025 | 17 | 29 | 50 Years | 75 Years | No |
| Soquel Drive | 41st Ave | Soquel Dr to 41st Ave Dedicated Right Turn Lane | Other | Construct a dedicated right turn lane | 01/2023 | 12/2025 | 02/2026 | 01/2027 | 17 | 29 | 50 Years | 75 Years | No |
| Soquel Drive | Aptos Creek Rd. | Soquel Drive Aptos Creek Rd. | Traffic Control Devices | Install traffic signal, thermoplastic striping, railroad crossing, sidewalk, curb ramps, and drainage improvements | 02/2017 | 05/2021 | 05/2021 | 12/2025 | 17 | 29 | 50 Years | 75 Years | No |
| Soquel Drive | La Fonda Av to State | Soquel Drive Multimodal Project | Road Maintenance and Rehabilitation | Resurfacing, sidewalk, and bike lane improvements, striping | 05/2021 | 06/2023 | 06/2023 | 12/1/2025 | 17 | 29 | 50 Years | 75 Years | No |
| Soquel Drive | PM 0.80 | Soquel Drive at Trout Gulch Road and Aptos Creek Road | Other | This project will include: Traffic Signals, Lights, | - | - | 06/2019 | 12/2025 | 17 | 29 | 50 Years | 75 Years | No |
| Soquel Drive | Robertson St. | Soquel Drive Robertson St. | Traffic Control Devices | Install traffic signal, thermoplastic striping and curb ramps | 02/2017 | 06/2023 | 08/2024 | 07/2026 | 17 | 29 | 50 Years | 75 Years | No |
| Soquel Drive | Soquel Ave | Soquel Dr to Soquel Ave Dedicated Right Turn Lane | Other | Construct a dedicated right turn lane | 01/2023 | 12/2025 | 02/2026 | 01/2027 | 17 | 29 | 50 Years | 75 Years | No |
| Soquel San Jose Rd | PM 1.25 | Soquel San Jose Rd PM 1.25 | Other | Slipouts - 60' long. soil nail retaining wall | 2/1/2019 | 5/2024 | 5/2024 | 08/2025 | 17 | 29 | 50 Years | 75 Years | No |
| Soquel San Jose Rd | PM 3.97 | Soquel San Jose Rd PM 3.97 | Other | This project will include: 2 slipouts, 20x50x10 & 50x150x10 | 2/1/2019 | 5/2024 | 5/2024 | 08/2025 | 17 | 29 | 50 Years | 75 Years | No |
| Soquel San Jose Rd | PM 5.91 | Soquel San Jose Rd PM 5.91 | Other | This project will include: Landscape Safety Installation (New), Pavement Improvement (New) Preparation of design and environmental documents for large Slipout (24' W x 115' L) - Recommend Roadway Reconstruction and Retaining Wall (TBD) Installation | 2/1/2019 | 5/2024 | 5/2024 | 08/2025 | 17 | 29 | 50 Years | 75 Years | No |
| Spanish Ranch Rl | PM 0.61 | SPANISH RANCH PM 0.61 | Other | This project will include: 20' long x 20' slipout, 2' into roadway. Recommend concrete restining wall on piles. | 01/2023 | 02/2023 | 05/31/2023 | 08/2025 | 17 | 29 | 50 Years | 75 Years | No |
| State Park Dr | Santa Cruz Av, Broadway, Center Ave | State Park Dr at Santa Cruz Av, Broadway, & Center Ave | Safety | Constrcut Road, Roadside, Streetscape, Lighting and Landscape Improvements | 05/2020 | 06/2025 | 08/2025 | 07/2026 | 17 | 29 | 50 Years | 75 Years | No |
| Stetson Rd | PM 0.18 | Stetson Rd PM 0.18 | Other | Cribwall and culvert failure completely cldsoing roadway. Replace culvert and construct new cribwall and roadway reconstruction | 02/2023 | 05/2025 | 06/2025 | 12/2025 | 17 | 29 | 50 Years | 75 Years | No |
| Stetson Rd | PM 1.08 | Stetson Rd PM 1.08 | Other | This project will include: Pavement Rehab/Repair (Existing), Storm Drain and/or Culvert Rehab/Repair (Existing) Preparation of design and environmental documents for repair to slipout - 55L x 18D and install soldier pile wall | 02/2023 | 05/2025 | 06/2025 | 12/2025 | 17 | 29 | 50 Years | 75 Years | No |
| Stetson Rd | PM 1.29 | Stetson Rd PM 1.29 | Other | This project will include: Road edge failure, 30' long undermining guardrail. Recommend extending adjacent soldier pile wall. | 02/2023 | 05/2025 | 06/2025 | 12/2025 | 17 | 29 | 50 Years | 75 Years | No |
| Swanton Rd | PM 0.72 | Swanton Rd PM 0.72 | Other | 8' Concrete Arch Culvert Failure and Slipout (64' L) - Temporary Creek Diversion System, SB Travelled Way and Shoulder Reconstruction and Retaining Wall (Soldier Pile) Installation | 02/2017 | 4/2026 | 5/2026 | 12/2026 | 17 | 29 | 50 Years | 75 Years | No |

Exhibit A
RMRA Project List for 2025/2026 Fiscal Year

| Project Road | Project Location | Project Title | Project Type | Project Description | Pre-Construction Estimated Start | Pre-Construction Estimated Completion | Construction Estimated Start | Construction Estimated Completion | State Senate | State Assembly | Estimated Minimum Useful Life | Estimated Maximum Useful Life | Additional Project Elements |
|-----------------------|------------------|--|--------------|---|----------------------------------|---------------------------------------|------------------------------|-----------------------------------|--------------|----------------|-------------------------------|-------------------------------|-----------------------------|
| Stetson Rd | PM 1.29 | STETSON RD PM 1.29 | Other | This project will include: Road edge failure, 30' long undermining guardrail. Recommend extending adjacent soldier pile wall. | 01/2023 | 02/2023 | 03/31/2023 | 08/2025 | 17 | 29 | 50 Years | 75 Years | No |
| Swanton Rd | PM 3.00 | Swanton Rd PM 3.00 | Other | 60' L slipout. Installing Soldier Pile Wall, Pavement and Shoulder Reconstruction | 02/2017 | 4/2026 | 5/2026 | 12/2026 | 17 | 29 | 50 Years | 75 Years | No |
| Swanton Rd | PM 5.27 | SWANTON RD PM 5.27 | Other | This project will include: Pavement Rehab/Repair (Existing) 200' long slipout. Recommend soldier pile wall and reconstruct portion of roadway | 02/2023 | 02/2023 | 05/31/2023 | 08/2025 | 17 | 29 | 50 Years | 75 Years | No |
| Trout Gulch Rd | PM 1.16 | Trout Gulch Rd PM 1.16 | Other | This project will include: Slipout (20' W x 40' L) - Recommend NB Traveled Way and Shoulder Reconstruction, Drainage Improvements and Retaining Wall (Soldier Pile) Installation | 2/2017 | 12/2020 | 6/2021 | 12/2027 | 17 | 29 | 50 Years | 75 Years | No |
| Trout Gulch Rd | PM 1.18 | Trout Gulch Rd PM 1.18 | Other | This project will include: Culvert Failure and Slipout (18' W x 25' L) - Recommend NB Traveled Way and Shoulder Reconstruction and 18' Culvert and Retaining Wall (Soldier Pile) Installation | 2/2017 | 12/2020 | 6/2021 | 12/2027 | 17 | 29 | 50 Years | 75 Years | No |
| Trout Gulch Rd | PM 1.85 | Trout Gulch Rd PM 1.85 | Other | This project will include: Slipout (20+/-' W x 50' L) - Recommend SB Traveled Way and Shoulder Reconstruction, RSP, and Retaining Wall (Soldier Pile) Installation | 2/2017 | 12/2020 | 6/2021 | 12/2027 | 17 | 29 | 50 Years | 75 Years | No |
| Trout Gulch Rd | PM 1.90 | Trout Gulch Rd PM 1.90 | Other | This project will include: Large Slipout (40+/-' L) Near Existing Cross Culvert - Recommend SB Traveled Way and Shoulder Reconstruction, 18' Culvert, RSP, and Retaining Wall (Soldier Pile) Installation | 2/2017 | 12/2020 | 6/2021 | 12/2027 | 17 | 29 | 50 Years | 75 Years | No |
| Trout Gulch Rd | PM 3.05 | Trout Gulch Rd PM 3.05 | Other | This project will include: Slipout (15+/-' W x 20' L) - Recommend NB Traveled Way and Shoulder Reconstruction, Drainage Improvements and Retaining Wall (Crib) Installation | 2/2017 | 12/2020 | 6/2021 | 12/2027 | 17 | 29 | 50 Years | 75 Years | No |
| Trout Gulch Rd | PM 2.90 | TROUT GULCH PM 2.90 | Other | This project will include: Storm Drain/Culvert Installation (New) Sink holes above culvert. Approx 48' culvert. Recommend culvert replacement with headwalls | 02/2023 | 04/2023 | 06/30/2023 | 08/2025 | 17 | 29 | 50 Years | 75 Years | No |
| Two Bar Rd | PM 1.13 | Two Bar Rd PM 1.13 | Other | This project will include: Storm Drain and/or Culvert Rehab/Repair (Existing) Slipout (40' W x 65' L) - Recommend NB/EB Traveled Lane and Shoulder Reconstruction, Drainage Improvements and Retaining Wall (Soldier Pile) Installation | 2/2017 | 12/2020 | 6/2021 | 12/2027 | 17 | 29 | 50 Years | 75 Years | No |
| Upper East Zayante Rd | PM 0.51 | UPPER ZAYANTE PM 0.51 | Other | This project will include: Storm Drain/Culvert Installation (New) | 02/2023 | 04/2023 | 04/30/2023 | 08/2025 | 17 | 29 | 50 Years | 75 Years | No |
| Upper East Zayante Rd | PM 1.18 | Upper East Zayante Rd PM 1.18 | Other | Road edge slipped out from clogged bleeder, tree failure with shoulder damage. Recommend shoulder pile wall and roadway reconstruction | 02/2023 | 05/2026 | 06/2026 | 12/2026 | 17 | 29 | 50 Years | 75 Years | No |
| Upper East Zayante Rd | PM 1.68 | Upper East Zayante PM 1.68 | Other | Slipout (45' L) Near Existing Retaining Wall (Crib) and Landslide - SB Traveled Way and Shoulder Reconstruction, Drainage Improvements and Retaining Wall (Soldier Pile) Installation | 02/2017 | 4/2025 | 5/2025 | 12/2025 | 17 | 29 | 50 Years | 75 Years | No |
| Upper East Zayante Rd | PM 2.51 | Upper East Zayante Rd PM 2.51 | Other | 30' long shoulder slipout. Recommend soldier pile repair | 02/2023 | 05/2025 | 06/2025 | 12/2025 | 17 | 29 | 50 Years | 75 Years | No |
| Upper Zayante Rd | PM 3.51 | UPPER ZAYANTE PM 3.51 | Other | This project will include: Pavement Rehab/Repair (Existing),Storm Drain/Culvert Installation (New) culvert replacement with rsp slope repair, 75' of paving | 02/2023 | 04/2023 | 04/30/2023 | 08/2025 | 17 | 29 | 50 Years | 75 Years | No |
| Valencia Rd | PM 0.04 | VALENCIA RD PM 0.04 (Trout Creek) | Other | This project will include: Pavement Rehab/Repair (Existing) 9' Culvert Failure and Roadway/Embankment Settling - Recommend Installation of Temporary Bridge, Replacement of Existing Culvert with a Box Culver and Roadway Reconstruction | 2/2017 | 12/2020 | 6/2021 | 12/2027 | 17 | 29 | 50 Years | 75 Years | No |
| Valencia Rd | PM 0.25 | Valencia Rd PM 0.25 | Other | Large slipout from above. Road damage about 50 long by 15' deep undermining edge of road and guardrails. Shoulder pile wall repair | 02/2023 | 05/2025 | 06/2025 | 12/2025 | 17 | 29 | 50 Years | 75 Years | No |
| Valencia Rd | PM 0.33 | VALENCIA RD PM 0.33 | Other | This project will include: Landscape Safety Rehab/Repair (Existing) Erosion at pipe discharge. Material moving down to the creek. Recommend slope repair and placement of rock slope protection | 03/2023 | 06/2023 | 03/31/2023 | 08/2025 | 17 | 29 | 50 Years | 75 Years | No |
| West Zayante Rd | PM 0.25 | W ZAYANTE PM 0.25 | Other | This project will include: Storm Drain and/or Culvert Rehab/Repair (Existing) | 02/2023 | 04/2023 | 04/30/2023 | 08/2025 | 17 | 29 | 50 Years | 75 Years | No |
| Zone 5 | All Roads | Road Drainage Master Plan Study - Zone 5 roads | Other | Road Drainage Master Plan Study - Zone 5 roads | 05/2020 | 07/2026 | - | - | 17 | 29 | 50 Years | 75 Years | No |