

84. Approve Road Maintenance and Rehabilitation Account project list for projects funded by Senate Bill 1, and take related actions ()



## **County of Santa Cruz Board of Supervisors**

### **Agenda Item Submittal**

**From:** Community Development and Infrastructure

**Subject:** Adopt RMRA Project List for FY 2025/2026

**Meeting Date:** June 24, 2025

**Formal Title:** Approve Road Maintenance and Rehabilitation Account project list for projects funded by Senate Bill 1, and take related actions

### **Recommended Actions**

1. Approve Road Maintenance and Rehabilitation Account project list for projects funded by Senate Bill 1 in Fiscal Year (FY) 2025-26; and
2. Authorize Community Development and Infrastructure to submit a copy of the approved Board package to the California Transportation Commission.

### **Executive Summary**

To receive SB 1 Funding, the County must formally adopt a Road Maintenance and Rehabilitation Account (RMRA) project list and provide proof of board approval of this list to the California Transportation Commission (CTC).

### **Discussion**

On April 28, 2017, the Governor signed SB 1 (Beall, Chapter 5, Statutes of 2017) to address basic road maintenance, rehabilitation, and critical safety needs on both the state highway system and local streets; specific allowable uses are defined in California Streets and Highways Code (SHC) 2030(B). This bill increases per gallon fuel excise taxes, diesel fuel sales taxes, increases vehicles registration fees, and provides for inflationary adjustments to tax rates in future years. The additional funds generated by these tax increases are deposited into the Road Maintenance and Rehabilitation Account (RMRA) and distributed to eligible cities and counties.

SB 1 stipulates that all agencies accepting RMRA funds must submit project reporting on an annual basis to the CTC. The CTC will give authorization for the State Controller to apportion RMRA funds to eligible agencies, any agency failing to submit required reporting to the CTC shall not receive RMRA funds. On August 16, 2017, the CTC adopted annual reporting guidelines (CTC Resolution G-17-23). Reporting consists of two parts: an RMRA project list to be submitted at the beginning of the fiscal year designating projects to be funded in that fiscal year, and an RMRA Project Expenditure Report at the end of the fiscal year which accounts for all RMRA expenditures which occurred in that fiscal year. Pursuant to California Streets and Highways Code (SHC) 2034(a)(1), the agency shall have the ability to fund projects that were not on the submitted RMRA project list without prior CTC authorization, so long as the project is consistent with the allowable uses outlined in SHC 2030(b) and is reported in the RMRA Project Expenditure Report.

The anticipated share of RMRA funds for the County for FY 2025-26 is \$7.0 million. Per SHC 2034(a)(1), the agency receiving RMRA funds shall provide documentation that the RMRA project list for all proposed projects to receive RMRA funding in that fiscal year has been approved by the Board of Supervisors in a regular meeting. Note that proof of approval of this project list for FY 2025-26 is due to the CTC by July 1, 2025,

and will be forwarded by Community Development and Infrastructure upon Board approval.

**Financial Impact**

RMRA funds in the amount of \$7.0 million will provide much needed revenue for County Road infrastructure repairs. These funds are held in the Road Fund (Funds 25100-25560) and distributed to various projects listed in the attached.

**Strategic Initiatives**

Equity Framework - County Facilities & Infrastructure  
Operational Plan - Reliable Transportation  
Climate Action - Transportation

**Submitted By:**

Matt Machado, Deputy CEO / Director of Community Development and Infrastructure

**Recommended By:**

Carlos J. Palacios, County Executive Officer

**Artificial Intelligence Acknowledgment:**

Artificial Intelligence (AI) did not significantly contribute to the development of this agenda item.

Exhibit A  
RMRA Project List for 2025/2026 Fiscal Year

Project Road	Project Location	Project Title	Project Type	Project Description	Pre-Construction Estimated Start	Pre-Construction Estimated Completion	Construction Estimated Start	Construction Estimated Completion	State Senate	State Assembly	Estimated Minimum Useful Life	Estimated Maximum Useful Life	Additional Project Elements
Anderson Dr & College Rd	Multiple	ANDERSON DR & COLLEGE RD MAR 23 CATB	Road Maintenance	This project will include: Pavement Rehab/Repair (Existing)	03/2023	03/2023	04/2023	08/2025	17	29	50 Years	75 Years	No
Aptos Beach Rd	PM 0.00	APTOS BEACH RD PM 0.00	Other	Slipout onto RR, Downdrain damage	03/2023	04/2023	03/01/2023	08/2025	17	29	50 Years	75 Years	No
Bean Creek Rd	PM 0.25	BEAN CREEK RD PM 0.25	Other	This project will include: 110' long slipout undercutting existing cribwall. Recommend soil nail wall to stabilize slope	03/2023	05/2025	04/30/2023	12/2025	17	29	50 Years	75 Years	No
Bean Creek Rd	PM 1.87	BEAN CREEK PM 1.87	Other	Roadway Slipout, 50' long x 20' tall, Tree Fell due to unstable steep slope, A lot of groundwater near toe of failure. Soldier pile wall repair	02/2023	04/2025	05/2025	12/2025	17	29	50 Years	75 Years	No
Bean Creek Rd	PM 2.10	BEAN CREEK PM 2.10	Other	This project will include: Landscape Safety Rehab/Repair (Existing), Storm Drain and/or Culvert Rehab/Repair (Existing)   Slipout (25'+/-' L) - Recommend SB (Outboard) Shoulder Reconstruction, Drainage Improvements and Retaining Wall (Soldier Pile) Installation	02/2023	04/2025	05/2025	12/2025	17	29	50 Years	75 Years	No
Bean Creek Rd	PM 2.39	BEAN CREEK RD PM 2.39	Other	24" cnp damaged and 20' of inlet crushed. Replace culvert and construct new headwalls	02/2023	05/2026	06/2026	12/2026	17	29	50 Years	75 Years	No
Bear Creek Rd	PM 0.20	BEAR CREEK RD PM 0.20	Other	This project will include: Pavement Rehab/Repair (Existing)   Large Slipout (75' L) and Damaged 48" Culvert - Recommend EB and WB Traveled Way and Shoulder Reconstruction, Rammed Culvert and Headwalls and Retaining Wall (Soldier Pile) Installation	03/2023	04/2023	03/01/2023	08/2025	17	29	50 Years	75 Years	No
Bear Creek Rd	PM 3.41	BEAR CREEK RD PM 3.41	Other	This project will include: Storm Drain and/or Culvert Rehab/Repair (Existing)	03/2023	04/2023	03/01/2023	08/2025	17	29	50 Years	75 Years	No
Bear Creek Rd	PM 4.18	Bear Creek Rd PM 4.18	Other	Culvert Collapsed. Deformed from bottom. Approx. 4'. Jack and bore new culvert under roadway	02/2023	05/2026	06/2026	12/2026	17	29	50 Years	75 Years	No
Bear Creek Rd	PM 6.73	Bear Creek Rd PM 6.73	Other	This project will include repair of a Road edge slipout 60' x 60'	03/2024	05/2027	06/2027	12/2027	17	29	50 Years	75 Years	No
Bear Creek Rd	PM 7.41	Bear Creek Rd PM 7.41	Other	Road Edge slipped out 30' long. Recommend shoulder pile wall	02/2023	05/2026	06/2026	12/2026	17	29	50 Years	75 Years	No
Browns Valley Rd	PM 2.93	Browns Valley Rd PM 2.93	Other	Slipout (10' L) - NB Shoulder Reconstruction, RSP and Drainage Improvements	02/2017	4/2025	5/2025	12/2025	17	29	50 Years	75 Years	No
Browns Valley Rd	PM 3.17	BROWNS VALLEY PM 3.17	Other	30' long slipout on edge of roadway. Soldier pile wall repair	03/2023	06/2023	06/2023	08/2025	17	29	50 Years	75 Years	No
Capitola Rd	7th Ave to 17th Ave	Capitola Rd Widening from 7th Ave to 17th Ave	Other	Widen Capitola Rd from two lanes to four	01/2023	12/2025	02/2026	01/2027	17	29	50 Years	75 Years	No
Capitola Rd	Chanticleer Ave to 30th Ave	Capitola Rd Widening from Chanticleer Ave to 30th Ave	Other	Widen Capitola Rd from two lanes to four	01/2023	12/2025	02/2026	01/2027	17	29	50 Years	75 Years	No
Casserty Rd	PM 2.93	Casserty Rd PM 2.93	Other	Slipout (20' W x 80' L) - EB/SB Shoulder Reconstruction, Drainage Improvements and Retaining Wall (Soldier Pile) Installation	02/2017	4/2025	5/2025	12/2025	17	30	50 Years	75 Years	No
Casserty Rd	PM 3.39	Casserty Rd PM 3.39	Other	Slipout (20' W x 20' L) - EB/SB Shoulder Reconstruction and Drainage Improvements	02/2017	4/2025	5/2025	12/2025	17	30	50 Years	75 Years	No
Cathedral Dr	PM 1.21	Cathedral dr PM 1.21	Other	This project will include: Storm Drain and/or Culvert Rehab/Repair (Existing)	02/2017	4/2025	5/2025	12/2025	17	30	50 Years	75 Years	No
China Grade Rd	PM 0.62	CHINA GRADE PM 0.62	Other	Culvert failure washed out roadway. Temporary bridge placed until bottomless arch culvert can be placed	01/2023	05/2026	01/30/2023	12/2026	17	29	50 Years	75 Years	No
Countywide	All Roads	Countywide Roadway Culvert Survey	Other	Countywide Roadway Culvert Survey	05/2020	07/2026	-	-	17	29	50	50	No
Countywide	All Roads	Countywide Roadside Vegetation Maintenance Project	Road Maintenance and Rehabilitation	Countywide Roadside Vegetation Maintenance Project	05/2020	07/2026	-	-	17	29	5	5	No
Countywide	All Roads	Countywide Roadside Drainage Maintenance Project	Road Maintenance and Rehabilitation	Countywide Roadside Drainage Maintenance Project	05/2020	07/2026	-	-	17	29	5	5	No
Countywide	All Roads	Countywide Culvert Maintenance Project	Road Maintenance and Rehabilitation	Countywide Culvert Maintenance Project	05/2020	07/2026	-	-	17	29	50	75	No
Countywide	All Roads	Countywide Roadbed Maintenance Project	Road Maintenance and Rehabilitation	Countywide Roadbed Maintenance Project	05/2020	07/2026	-	-	17	29	10	20	No
Countywide	All Roads	Countywide Striping Maintenance Project	Safety	Countywide Striping Maintenance Project	05/2020	07/2026	-	-	17	29	5	5	No
Countywide	All Roads	Countywide Signage Maintenance Project	Safety	Countywide Signage Maintenance Project	05/2020	07/2026	-	-	17	29	10	20	No
Countywide	All Roads	Countywide Guardrail Maintenance Project	Safety	Countywide Guardrail Maintenance Project	05/2020	07/2026	-	-	17	29	50	75	No
Countywide	All Roads	Countywide Pavement Planning/Grinding	Road Maintenance & Rehabilitation	This project will include: Pavement Rehab/Repair (Existing),Paving and/or Striping Rehab/Repair (Existing Safety)	05/2020	07/2026	-	-	17	29	50 Years	75 Years	No
Cox Rd	PM 1.71	COX RD PM 1.71	Other	160' long slipout halfway into road. Soldier pile repair	01/2023	04/2023	04/30/2023	08/2025	17	29	50 Years	75 Years	No
Cox Rd	PM 1.93	COX RD PM 1.93	Other	This project will include: Slipout (40' L) - Recommend WB Shoulder Reconstruction, Drainage Improvements (New Storm Drain Through Wall) and Retaining Wall (Soldier Pile) Installation	01/2023	05/2027	06/2027	12/2027	17	29	50 Years	75 Years	No
Cox Rd	PM 2.03	COX RD PM 2.03	Other	This project will include: Slipout (60'W x 100' L) - Recommend WB Traveled Way and Shoulder Reconstruction, Drainage Improvements, RSP and Retaining Wall (Soldier Pile)	01/2023	04/2023	04/30/2023	08/2025	17	29	50 Years	75 Years	No
Day Valley Rd	PM 1.18	Day Valley Rd PM 1.18 at Cox Rd	Other	This project will include repair of a Road edge slipout 25' x 10'	03/2024	05/2027	06/2027	12/2027	17	29	50 Years	75 Years	No
E Zayante Rd	PM 1.01	E Zayante Rd PM 1.01	Other	This project will include repair of a Road edge slipout 20' x 40'	03/2024	05/2027	06/2027	12/2027	17	29	50 Years	75 Years	No
E Zayante Rd	PM 4.48	E ZAYANTE PM 4.48	Other	15' long by 8' tall slipout on edge of road. Soldier pile repair	01/2023	04/2023	3/15/2023	12/2027	17	29	50 Years	75 Years	No
E Zayante Rd	PM 4.69	E ZAYANTE PM 4.69	Other	70' long by 15' tall slipout 6' into roadway. 18" HDPE crossing at location. One lane closed. Soldier pile repair	01/2023	04/2023	3/15/2023	12/2027	17	29	50 Years	75 Years	No
E. Cliff Dr	17th Ave to Palisades Ave	E. Cliff Dr Pedestrian Improvements from 17th Ave to Palisades Ave	Other	Construct pedestrian and bike improvements	01/2023	06/2026	08/2026	01/2027	17	29	50 Years	75 Years	No
E. Cliff Dr	7th Ave to 14th Ave	E. Cliff Dr Pedestrian Improvements from 7th Ave to 14th Ave	Other	Construct pedestrian and bike improvements	01/2023	06/2026	08/2026	01/2027	17	29	50 Years	75 Years	No
Empire Grade	UCSC ARBORETU	EMPIRE GRADE @ UCSC ARBORETUM	Other	40' long slipout on road shoulder. Geogrid reinforced slope repair	01/2023	04/2023	01/30/2023	08/2025	17	29	50 Years	75 Years	No
Eureka Canyon Rd	PM 0.35	EUREKA CANYON PM 0.35	Other	40 foot long slipout, 3 ft into road. Soldier pile repair	01/2023	04/0225	05/2025	12/2025	17	29	50 Years	75 Years	No
Eureka Canyon Rd	PM 3.16	Eureka Canyon Rd PM 3.16	Other	Culvert Failure and Slipout (12' L) - SB (Outboard) Shoulder Reconstruction, Drainage Improvements including 36" Culvert Replacement and Retaining Wall (Soldier Pile) Installation	02/2017	4/2025	5/2025	12/2025	17	29	50 Years	75 Years	No
Eureka Canyon Rd	PM 3.36	Eureka Canyon Rd PM 3.36	Other	Major Slipout (20'+/-' W x 70' L) with Potential Deep Seated Landslide - NB Traveled Way and Shoulder Reconstruction and Retaining Wall (Soldier Pile) Installation	02/2017	4/2025	5/2025	12/2025	17	29	50 Years	75 Years	No
Eureka Canyon Rd	PM 3.50	Eureka Canyon Rd PM 3.50	Other	Tree Fell on causing 25' long slipout on edge of roadway. RSP embankment repair	03/2023	05/2025	05/2025	12/2025	17	29	50 Years	75 Years	No
Eureka Canyon Rd	PM 4.28	Eureka Canyon Rd PM 4.28	Other	This project will include: Cost Estimating, Document Preparation, Environmental Study/Documents, Preliminary Design	03/2023	05/2025	05/2025	12/2025	17	29	50 Years	75 Years	No

Exhibit A  
RMRA Project List for 2025/2026 Fiscal Year

Project Road	Project Location	Project Title	Project Type	Project Description	Pre-Construction Estimated Start	Pre-Construction Estimated Completion	Construction Estimated Start	Construction Estimated Completion	State Senate	State Assembly	Estimated Minimum Useful Life	Estimated Maximum Useful Life	Additional Project Elements
Eureka Canyon Rd	PM 4.67	Eureka Canyon Rd PM 4.67	Other	Roadway/Embankment Settling (20' L) Caused by Fallen Trees and Near Existing Retaining Wall (Crib) - NB and SB Traveled Way and Shoulder Reconstruction, Drainage Improvements including RSP and Retaining Wall (Soldier Pile) Installation	02/2017	4/2025	5/2025	12/2025	17	29	50 Years	75 Years	No
Eureka Canyon Rd	PM 5.05	Eureka Canyon Rd PM 5.05	Other	Slipout (25' L) - SB Shoulder Reconstruction, Drainage Improvements, RSP and Retaining Wall (Soldier Pile) Installation	02/2017	4/2025	5/2025	12/2025	17	29	50 Years	75 Years	No
Eureka Canyon Rd	PM 5.31	Eureka Canyon Rd PM 5.31	Other	Slipout (25' L) - NB Shoulder Reconstruction, RSP and Retaining Wall (Soldier Pile) Installation	02/2017	4/2025	5/2025	12/2025	17	29	50 Years	75 Years	No
Eureka Canyon Rd	PM 5.33	Eureka Canyon Rd PM 5.33	Other	25' long slipout, Rock wall repair with roadway reconstruction	02/2017	05/2025	05/2025	12/2025	17	29	50 Years	75 Years	No
Eureka Canyon Rd	PM 6.50	Eureka Canyon Rd PM 6.50	Other	This project will include: Cost Estimating, Document Preparation, Environmental Study/Documents, Preliminary Design, Right of Way	02/2017	05/2025	05/2025	12/2025	17	29	50 Years	75 Years	No
Eureka Canyon Rd	PM 8.39	Eureka Canyon Rd PM 8.39	Other	Slipout (50' L) - SB Shoulder Reconstruction, Drainage Improvements, RSP and Retaining Wall (Soldier Pile) Installation	02/2017	4/2025	5/2025	12/2025	17	29	50 Years	75 Years	No
Gaffey Rd	PM 0.03, 0.04, 0.08	Gaffey Rd PM 0.03, 0.04, 0.08	Other	Slipout (20' L) - EB (Outboard) Embankment Reconstruction, RSP and Drainage Improvements	02/2017	05/2022	06/2026	12/2026	17	30	50 Years	75 Years	No
Gaffey Rd	PM 0.08	GAFFEY RD PM 0.08	Other	Damaged culvert to be replaced. Includes fish passage.	02/2023	05/2026	06/2027	12/2027	17	29	50 Years	75 Years	No
Glen Canyon Rd	PM 0.39	Glen Canyon Rd PM 0.39	Other	Sink Hole found near culvert inlet. Slipline or replace culvert	02/2023	05/2026	06/2026	12/2026	17	29	50 Years	75 Years	No
Glen Haven Rd	PM 0.70	GLEN HAVEN PM 0.70	Other	Loss of road shoulder app. 100' long. Soldier pile repair.	02/2023	05/2023	01/30/2023	08/2025	17	29	50 Years	75 Years	No
Glenwood Cut-off	PM 0.02	Glenwood Cut-off PM 0.02	Other	Slipout (4' W x 35' L) - WB (Outboard) Traveled Way and Shoulder Reconstruction, Drainage Improvements and Retaining Wall (Crib) Installation	02/2017	4/2025	5/2025	12/2025	17	29	50 Years	75 Years	No
Glenwood Dr	PM 2.02	Glenwood Dr PM 2.02	Other	Erosion Under Existing Retaining Wall (Soldier Pile) - Backfill of Eroded Slope, Drainage Improvements and Erosion Control	02/2017	4/2025	5/2025	12/2025	17	29	50 Years	75 Years	No
Glenwood Dr	PM 2.58	GLENWOOD DR PM 2.58	Other	35' long slipout along creek bank with undermining of roadway. Recommend cribwall and roadway reconstruction	02/2023	05/2023	05/31/2023	08/2025	17	29	50 Years	75 Years	No
Glenwood Dr	PM 2.60	GLENWOOD DR PM 2.60	Other	This project will include: Retaining Wall Failure Caused by Erosion Under Footing, Adjacent to Existing Retaining Walls (Crib) - Recommend Backfill Eroded Footing, Install Drainage	02/2023	05/2023	05/31/2023	08/2025	17	29	50 Years	75 Years	No
Glenwood Dr	PM 2.62	GLENWOOD DR PM 2.62	Other	75' long slipout along creek bank with undermining of roadway. Recommend cribwall and roadway reconstruction	02/2023	05/2023	05/31/2023	08/2025	17	29	50 Years	75 Years	No
Glenwood Dr	PM 2.91	GLENWOOD DR PM 2.91	Other	Pavement Improvement (New), Right of Way Acquisition, Storm Drain and/or Culvert Rehab/Repair (Existing), Storm Drain/Culvert Installation (New)	02/2023	05/2023	05/31/2023	08/2025	17	29	50 Years	75 Years	No
Granite Creek Rd	PM 0.06	Granite Creek Rd PM 0.06	Other	This project will include: Cost Estimating, Document Preparation, Environmental Study/Documents, Preliminary Design	02/2017	4/2025	5/2025	12/2025	17	29	50 Years	75 Years	No
Granite Creek Rd	PM 0.47	Granite Creek Rd PM 0.47	Other	Slipout (50' L) - NB Shoulder Reconstruction, RSP and Overside Drain Replacement	02/2017	4/2025	5/2025	12/2025	17	29	50 Years	75 Years	No
Granite Creek Rd	PM 0.55	Granite Creek Rd PM 0.55	Other	This project will include: Cost Estimating, Document Preparation, Environmental Study/Documents, Preliminary Design	02/2017	4/2025	5/2025	12/2025	17	29	50 Years	75 Years	No
Granite Creek Rd	PM 2.10	Granite Creek Rd PM 2.10	Other	Slipout (3'-6" W x 10' L) - SB Traveled Way and Shoulder Reconstruction and Placement of RSP	02/2017	4/2025	11/11/2023	12/2027	17	29	50 Years	75 Years	No
Green Valley Rd	Holohan Rd to Mesa Verde Dr	Green Valley Rd Multi-Use Path	Other	Construct a multi-use path with improved bus stops and trash receptacles	07/2022	07/2023	05/2024	07/2025	17	30	50 Years	75 Years	Yes
Green Valley Rd	PM 1.85	Green Valley Rd PM 1.85	Other	Large Sinkhole Caused by Culvert Failure - 72" Culvert and Headwalls and Roadway Reconstruction	02/2017	05/2022	05/2022	08/2025	17	29	50 Years	75 Years	No
Green Valley Rd	PM 2.34	Green Valley Rd PM 2.34	Other	25' long x 15' deep slipout. Edge of road undermined 1-2 feet. Recommend shoulder pile wall	02/2023	05/2026	06/2026	12/2026	17	29	50 Years	75 Years	No
Hazel Dell Rd	PM 2.00	Hazel Dell Rd PM 2.00	Other	Large Slipout/ landslide 85' long x 10' deep, slip potential - Retaining Wall Installation	02/2017	05/2022	05/2022	08/2025	17	29	50 Years	75 Years	No
Hazel Dell Rd	PM 2.08	Hazel Dell Rd PM 2.08	Other	Large Slipout, Roadway Reconstruction, Drainage Improvements and Retaining Wall (TBD) Installation	02/2017	05/2022	05/2022	08/2025	17	29	50 Years	75 Years	No
Hazel Dell Rd	PM 2.13	Hazel Dell Rd PM 2.13	Other	Slipout - 30' wide by 10' deep, Shoulder Reconstruction and Retaining Wall (Soldier Pile) Installation	02/2017	05/2022	05/2022	08/2025	17	29	50 Years	75 Years	No
Hazel Dell Rd	PM 2.16	Hazel Dell Rd PM 2.16	Other	Settling Roadway 85' long, possible cross culvert damage, Culvert Replacement, Roadway and Shoulder Reconstruction and Retaining Wall (Soldier Pile) Installation	02/2017	05/2022	05/2022	08/2025	17	29	50 Years	75 Years	No
Hazel Dell Rd	PM 2.21	Hazel Dell Rd PM 2.21	Other	Failing Crib Wall - 50' long x 12' tall, Shoulder Reconstruction and Retaining Wall Structure	02/2017	05/2022	05/2022	08/2025	17	29	50 Years	75 Years	No
Hazel Dell Rd	PM 2.35	HAZEL DELL PM 2.35	Other	50' long slipout half way into roadway. Soil nail wall to stabilize and then MSE wall.	02/2023	05/2025	05/31/2023	12/2025	17	29	50 Years	75 Years	No
Hazel Dell Rd	PM 2.37	Hazel Dell Rd PM 2.37	Other	Slipout with Embankment Settlement, Shoulder Reconstruction and Retaining Wall	02/2017	05/2021	05/2022	08/2025	17	29	50 Years	75 Years	No
Hazel Dell Rd	PM 2.57	HAZEL DELL RD PM 2.57	Other	Slipout 50' long, Soldier pile repair with roadway reconstruction	02/2023	05/2026	06/2026	12/2026	17	29	50 Years	75 Years	No
Hazel Dell Rd	PM 2.58	Hazel Dell Rd PM 2.58	Other	Failed Crib Wall, Reconstruct Damaged Shoulder and Roadway, Retaining Wall (Soldier Pile) Installation	02/2017	05/2021	05/2022	08/2025	17	29	50 Years	75 Years	No
Hazel Dell Rd	PM 2.61	HAZEL DELL RD PM 2.61	Other	This project will include: Slipout 24' long. Recommend soldier pile wall.	02/2023	04/2023	6/15/2023	12/2027	17	29	50 Years	75 Years	No
Hazel Dell Rd	PM 2.63	HAZEL DELL RD PM 2.63	Other	65' long slipout half way into roadway. Soldier pile wall repair	02/2023	05/2023	5/17/2023	12/2027	17	29	50 Years	75 Years	No
Hazel Dell Rd	PM 3.43	Hazel Dell Rd PM 3.43	Other	This project will include repair of a Road edge slipout 6' x 6'	03/2024	05/2027	06/2027	12/2027	17	29	50 Years	75 Years	No
Highland Way	PM 0.70	Highland Way PM 0.70	Other	30' long by 5' tall shoulder slipout 6' into roadway, Caused by fallen tree, RSP repair with roadway reconstruction	02/2023	05/2026	06/2026	12/2026	17	29	50 Years	75 Years	No
Highland Way	PM 2.40	Highland Way PM 2.40	Other	Road sinking and shifting 50x10. Recommend reconstruction roadway and geogrid slope reinforcement	02/2023	05/2026	06/2026	12/2026	17	29	50 Years	75 Years	No
Highland Way	PM 3.73	HIGHLAND WAY PM 3.73	Other	Roadway damage on both sides of recently constructed soldier pile wall. Recommend extending soldier pile walls with roadway reconstruction	02/2023	04/2023	8/3/2023	12/2027	17	29	50 Years	75 Years	No
Highland Way	PM 3.91	HIGHLAND WAY PM 3.91	Other	This project will include: Slipout (10+/-' W x 25' L) - Recommend SB (Outboard) Traveled Way and Shoulder Reconstruction, Drainage Improvements and Retaining Wall (Soldier Pile) Installation	02/2023	04/2023	03/31/2023	08/2025	17	29	50 Years	75 Years	No
Highland Way	PM 4.55	HIGHLAND WAY PM 4.55	Other	50' long slipout taking out most of roadway near culvert. MSE wall repair	02/2023	05/2023	5/10/2023	12/2027	17	29	50 Years	75 Years	No
Holohan Rd	Green Valley Rd to Hwy 152	Holohan Road Multi-Use Path	Other	Construct a multi-use path	06/2023	06/2025	08/2025	07/2026	17	30	50 Years	75 Years	No
Holohan Rd and College Rd	Hwy 152	Holohan Road and College Road at Hwy 152	Traffic Control Devices	Traffic signal, sidewalk and drainage improvements, striping	02/2017	05/2022	05/2022	12/2025	17	30	50 Years	75 Years	No
Hopkins Gulch Rd	#4	Hopkins Gulch Rd #4	Other	This project will include: Document Preparation, Environmental Study/Documents, Feasibility Study, Preliminary Design, Right of Way	02/2023	05/2023	05/31/2023	08/2025	17	29	50 Years	75 Years	No

Exhibit A  
RMRA Project List for 2025/2026 Fiscal Year

Project Road	Project Location	Project Title	Project Type	Project Description	Pre-Construction Estimated Start	Pre-Construction Estimated Completion	Construction Estimated Start	Construction Estimated Completion	State Senate	State Assembly	Estimated Minimum Useful Life	Estimated Maximum Useful Life	Additional Project Elements
Ice Cream Grade	PM 1.24	Ice Cream Grade Rd PM 1.24	Other	Road Edge failure above culvert wall above wingwall is failing. Construct new headwall	02/2023	05/2026	06/2026	12/2026	17	29	50 Years	75 Years	No
Ice Cream Grade	PM 1.36	Ice Cream Grade Rd PM 1.36	Other	Slipout - 105'L x 8'D - install soldier pile wall	02/2017	04/2022	06/2022	08/2025	17	29	50 Years	75 Years	No
Ice Cream Grade	PM 1.55	Ice Cream Grade Rd PM 1.55	Road Maintenance & Rehabilitation	42' L slipout, install wall, pavement repair, erosion control	02/2017	04/2022	06/2022	08/2025	17	29	50 Years	75 Years	No
Ice Cream Grade	PM 1.60	Ice Cream Grade Rd PM 1.60	Other	Road/Embankment Settling (12' W x 100' L) - Recommend EB Traveled Way and Shoulder Reconstruction, Drainage Improvements and Retaining Wall (Soldier Pile) Installation	02/2017	04/2022	06/2022	08/2025	17	29	50 Years	75 Years	No
Jamison Creek Rd	PM 1.61	Jamison Creek Road PM 1.61	Other	Slipout - 25'L x 10'D - Roadway and Shoulder Reconstruction and Installation of Soldier Pile Wall	02/2017	4/2024	5/2024	08/2025	17	29	50 Years	75 Years	No
Jarvis Rd	PM 0.64	Jarvis Rd PM 0.64	Other	Slipout (6' W x 20+/-') - NB (Outboard) Traveled Way and Shoulder Reconstruction, Earth backfill and Downdrain	02/2017	4/2025	06/2026	12/2026	17	29	50 Years	75 Years	No
Jarvis Rd	PM 0.68	Jarvis Rd PM 0.68	Other	Culvert Failure & Roadway/Embankment Settling - Roadway Reconstruction and Drainage Improvements including 18" Culvert and Headwalls - SB Shoulder Reconstruction, Drainage Improvements and Retaining Wall (Soldier Pile) Installation,	02/2017	4/2025	06/2026	12/2026	17	29	50 Years	75 Years	No
Jarvis Rd	PM 1.02, 1.04, 1.07	Jarvis Rd PM 1.02, 1.04, 1.07	Other	PM 1.02 - Slipout (20+/-' W x 60' L) - SB Shoulder Reconstruction, Drainage Improvements and Retaining Wall (Soldier Pile) Installation, PM 1.04 - Slipout (6' W x 40' L) - SB (Outboard) Traveled Way and Shoulder Reconstruction, Drainage Improvements and Retaining Wall (Crib) Installation	02/2017	4/2025	06/2026	12/2026	17	29	50 Years	75 Years	No
Jarvis Rd	PM 1.66	Jarvis Rd PM 1.66	Other	Culvert Failure & Roadway/Embankment Settling - Roadway Reconstruction and Drainage Improvements including 18" Culvert and Headwalls	02/2017	4/2025	5/2025	12/2025	17	29	50 Years	75 Years	No
Kings Creek Rd	PM 1.65	Kings Creek Rd PM 1.65	Other	Slipout and Damaged Downdrain - Installation of Gabion Baskets or RSP, Backfill and Reinstall Culvert	02/2017	4/2025	5/2025	12/2025	17	29	50 Years	75 Years	No
Kings Creek Rd	PM 3.03	Kings Creek Rd PM 3.03	Other	Slipout (40' L) and Landslide - Roadway Reconstruction, Drainage Improvements and Retaining Wall (Soldier Pile) Installation	02/2017	4/2025	5/2025	12/2025	17	29	50 Years	75 Years	No
Kings Creek Rd	PM 3.16	Kings Creek Rd PM 3.16	Other	Slipout and Roadway/Embankment Settling - Roadway Reconstruction, Drainage Improvements, and Retaining Wall (Stitch Pile) Installation	02/2017	4/2025	5/2025	12/2025	17	29	50 Years	75 Years	No
Lakeview Dr	PM 0.42	LAKEVIEW DR PM 0.42	Other	Landscape Safety Installation (New).Pavement Rehab/Repair (Existing)   20' long shoulder slipout due to fallen tree. Recommend soldier pile wall and reconstruct portion of roadway.	02/2023	05/2023	05/31/2023	08/2025	17	29	50 Years	75 Years	No
Lakeview Dr RI	PM 0.52	LAKEVIEW DR PM 0.52	Other	This project will include: Storm Drain/Culvert Installation (New)	02/2023	05/2023	05/31/2023	08/2025	17	29	50 Years	75 Years	No
Little Basin Rd	PM 0.64	Little Basin Rd PM 0.64	Other	Slipout (35' L) - EB (Outboard) Roadway Reconstruction, Drainage Improvements and Retaining Wall (Soldier Pile) Installation	02/2017	6/2024	7/2024	08/2025	17	29	50 Years	75 Years	No
Little Basin Rd	PM 0.85	Little Basin Rd PM 0.85	Other	Slipout (80' L) - SB (Outboard) Traveled Way and Shoulder Reconstruction, Drainage Improvements and Retaining Wall (Soldier Pile) Installation	02/2017	6/2024	7/2024	08/2025	17	29	50 Years	75 Years	No
Little Basin Rd	PM 1.50	Little Basin Rd PM 1.50	Other	30' long slipout along shoulder, recommend soldier pile wall	02/2023	05/2026	06/2026	12/2026	17	29	50 Years	75 Years	No
Lockhart Gulch Rd	Nelson Rd	Lockhart Gulch at Nelson Rd - Slipout	Other	20' long shoulder slipout. Cribwall repair	03/2023	06/2023	03/31/2023	08/2025	17	29	50 Years	75 Years	No
Lockhart Gulch Rd	PM 0.24	Lockhart Gulch Rd PM 0.24	Other	Slipout (55'L) - NB Shoulder Reconstruction, Drainage Improvements, and Retaining Wall (Crib) Installation	02/2017	5/2023	5/2023	08/2025	17	29	50 Years	75 Years	No
Lockhart Gulch Rd	PM 0.35	LOCKHART GULCH PM 0.35	Other	60' long by 10' tall shoulder slipout. Cribwall repair recommended.	02/2023	05/2025	5/31/2025	12/2025	17	29	50 Years	75 Years	No
Lockhart Gulch Rd	PM 1.68	LOCKHART GULCH PM 1.68	Other	This project will include: Landscape Safety Installation (New).Paving and/or Striping Installation (New Safety)   50' slipout, half of road gone. Recommend soldier pile wall with roadway reconstruction.	02/2023	05/2023	3/16/2023	12/2027	17	29	50 Years	75 Years	No
Lodge Rd	PM 1.07	Lodge Road PM 1.07	Other	60' longslipout. Only 5' left of road. Recommend shoulder pile or soil nail wall	02/2023	05/2026	06/2026	12/2026	17	29	50 Years	75 Years	No
Loma Prieta Av	PM 2.82	Loma Prieta Av PM 2.82	Other	This project will include: Storm Drain and/or Culvert Rehab/Repair (Existing)   Slipout (20'L) - Recommend SB Shoulder Reconstruction, Drainage Improvements, and Retaining Wall (Soldier Pile) Installation	02/2017	05/2025	05/2025	12/2025	17	29	50 Years	75 Years	No
Loma Prieta Wy	PM 3.33	Loma Prieta Wy PM 3.33	Other	This project will include: Storm Drain and/or Culvert Rehab/Repair (Existing)   Slipout (60' L) - Recommend EB Traveled Way and Shoulder Reconstruction, Drainage Improvements and Retaining Wall (Soldier Pile) Installation	02/2017	05/2025	05/2025	12/2025	17	29	50 Years	75 Years	No
Lompico Rd	PM 0.22	Lompico Rd PM 0.22	Other	This project will include: Pavement Rehab/Repair (Existing)   Slipout (40' W x 100' L) - Recommend SB Traveled Way and Shoulder Reconstruction and Retaining Wall (Soldier Pile) Installation	02/2017	4/2025	5/2025	12/2027	17	29	50 Years	75 Years	No
Lompico Rd	PM 0.70	Lompico Rd PM 0.70	Other	This project will include: Cost Estimating, Document Preparation, Environmental Study/Documents, Preliminary Design	02/2017	4/2025	5/2027	12/2027	17	29	50 Years	75 Years	No
Lompico Rd	PM 0.80	Lompico Rd PM 0.80	Other	30' long slipout due to tree falling on shoulder of road. RSP repair	02/2017	05/2025	05/2025	12/2025	17	29	50 Years	75 Years	No
Lompico Rd	PM 1.09	LOMPICO RD PM 1.09	Other	This project will include: Landscape Safety Installation (New)	02/2023	05/2025	5/31/2025	12/2025	17	29	50 Years	75 Years	No
Lompico Rd	PM 1.22	Lompico Rd PM 1.22	Other	Slipout (45' L) - NB Shoulder Reconstruction, Drainage Improvements, RSP and Retaining Wall (Crib) Installation	02/2017	4/2025	5/2025	12/2025	17	29	50 Years	75 Years	No
Lompico Rd	PM 2.38	Lompico Rd PM 2.38	Other	Slipout (10' W x 25' L) - NB Traveled Way and Shoulder Reconstruction and Installation of Retaining Wall (Crib)	02/2017	4/2025	5/2026	12/2026	17	29	50 Years	75 Years	No
Lompico Rd	PM 1.85	LOMPICO RD PM 1.85	Other	This project will include: Landscape Safety Installation (New)   80' x 20' Slipout. Recommend rock slope protection backfill to stabilize slope.	01/2023	02/2023	02/28/2023	08/2025	17	29	50 Years	75 Years	No
Lompico Rd	West Dr	LOMPICO RD @ WEST DR	Other	This project will include: Landscape Safety Installation (New)	01/2023	02/2023	02/28/2023	08/2025	17	29	50 Years	75 Years	No
Love Creek Rd	PM 0.35	Love Creek Rd PM 0.35	Other	This project will include: Landscape Safety Rehab/Repair (Existing), Paving and/or Striping Rehab/Repair (Existing Safety)   35' long slipout 4' into roadway. Recommend cribwall repair	02/2017	4/2025	5/2025	12/2027	17	29	50 Years	75 Years	No
Lower Highland Wy	PM 0.34	Lower Highland Wy PM 0.34	Other	This project will include: Slipout (18' W x 65'L) - Recommend Traveled Way and Shoulder Reconstruction, RSP, and Retaining Wall (Soldier Pile) Installation	02/2017	4/2025	5/2025	12/2027	17	29	50 Years	75 Years	No
Main St	BATES CREEK	MAIN ST @ BATES CREEK	Other	Large culvert failure with road washout. Construct reinforced concrete box culvert allowing fish passage.	03/2023	06/2023	03/31/2023	12/2027	17	29	50 Years	75 Years	No

Exhibit A  
RMRA Project List for 2025/2026 Fiscal Year

Project Road	Project Location	Project Title	Project Type	Project Description	Pre-Construction Estimated Start	Pre-Construction Estimated Completion	Construction Estimated Start	Construction Estimated Completion	State Senate	State Assembly	Estimated Minimum Useful Life	Estimated Maximum Useful Life	Additional Project Elements
Miller Cut-off Rd	PM 0.47	Miller Cut-off Rd PM 0.47	Other	Repair combined with Miller Cutoff 0.49. Slipout (15' W x 85'L) Adjacent to Existing Crib Wall (Installed 2016) - NB (Outboard) Traveled Way and Shoulder Reconstruction, Drainage Improvements and Retaining Wall (Soldier Pile) Installation	02/2017	4/2025	5/2025	12/2025	17	29	50 Years	75 Years	No
Miller Cut-off Rd	PM 0.49	Miller Cut-off Rd PM 0.49	Other	Slipout (15' W x 85'L) Adjacent to Existing Crib Wall (Installed 2016) - NB (Outboard) Traveled Way and Shoulder Reconstruction, Drainage Improvements and Retaining Wall (Soldier Pile) Installation	02/2017	4/2025	5/2025	12/2025	17	29	50 Years	75 Years	No
Morrell Rd	PM 0.50	Morrell Rd PM 0.50	Other	This project will include: Cost Estimating, Document Preparation, Environmental Study/Documents, Preliminary Design, Right of Way   Slipout and Culvert Failure-Recommend Roadway Reconstruction, 18" and 24" Culvert Replacement and Retaining Wall (Soldier Pile) Installation	03/2025	05/2026	4/30/2027	12/2027	17	29	50 Years	75 Years	No
Mt Bache Rd	PM 0.50	MT BACHE RD PM 0.50	Other	This project will include: Storm Drain/Culvert Installation (New)	02/2023	04/2023	04/30/2023	08/2025	17	29	50 Years	75 Years	No
Mt Charlie Rd	PM 0.26	Mt Charlie Road PM 1.26	Other	This project will include: Pavement Rehab/Repair (Existing), Storm Drain and/or Culvert Rehab/Repair (Existing)   Pier & Lagging Wall w/ tiebacks, guard rail, ac dike, drainage facilities, pavement repair, erosion control	02/2023	04/2023	04/30/2023	08/2025	17	29	50 Years	75 Years	No
Mt Charlie Rd	PM 1.66	Mt Charlie Road PM 1.66	Other	100' roadway slipout with road closure. Recommend soldier pile wall with road reconstruction	02/2023	05/2025	06/2025	12/2025	17	29	50 Years	75 Years	No
Mt Charlie Rd	PM 1.94	Mt Charlie Road PM 1.94	Other	50' long slipout near culvert. Soldier pile wall repair	02/2023	05/2025	06/2025	12/2025	17	29	50 Years	75 Years	No
Mt Charlie Rd	PM 4.48	Mt Charlie Road PM 4.48	Other	This project will include repair of a Road edge slipout 40' long	03/2024	05/2027	06/2027	12/2027	17	29	50 Years	75 Years	No
Mountain View Rd	PM 0.25	Mountain View Rd PM 0.25	Other	This project will include repair of lost road shoulder	03/2024	05/2027	06/2027	12/2027	17	29	50 Years	75 Years	No
Nelson Rd	PM 0.43	Nelson Rd PM 0.43	Other	3 Slipouts (Varying 30 to 50' L) - NB Traveled Way and Shoulder Reconstruction, Drainage Improvements and Retaining Wall (Soldier Pile) Installation	02/2017	4/2024	5/2024	08/2025	17	29	50 Years	75 Years	No
Nelson Rd	PM 0.44	Nelson Rd PM 0.44	Other	Road washout due to clogged culvert/flooding. Place new culvert, place headwalls, and reconstruct roadway	02/2017	4/2025	5/2026	12/2026	17	29	50 Years	75 Years	No
Mountain View Rd	PM 1.88	North Rodeo Gulch Rd PM 1.88	Other	This project will include repair of a road edge following tree fall and uprooting	03/2024	05/2027	06/2027	12/2027	17	29	50 Years	75 Years	No
Mountain View Rd	PM 2.58	North Rodeo Gulch Rd PM 2.58	Other	This project will include repair of a road edge following tree fall and uprooting	03/2024	05/2027	06/2027	12/2027	17	29	50 Years	75 Years	No
Mountain View Rd	PM 2.70	North Rodeo Gulch Rd PM 2.70	Other	This project will include repair of 3 sections of road edge damage: 15x4, 33x4, 2x2 feet	03/2024	05/2027	06/2027	12/2027	17	29	50 Years	75 Years	No
North Rodeo Gulch	PM 3.77	North Rodeo Gulch Road PM 3.77	Other	50' long slipout into roadway. Lane closed. Soldier pile wall repair	02/2023	05/2025	06/2025	12/2025	17	29	50 Years	75 Years	No
North Rodeo Gulch	PM 3.82	North Rodeo Gulch PM 3.82	Other	Slipout (6' W x 50' L) - SB Traveled Way and Shoulder Reconstruction, Drainage Improvements and Retaining Wall (Soldier Pile) Installation	02/2017	4/2025	5/2025	12/2025	17	29	50 Years	75 Years	No
Old Bear Creek Rd	PM 0.01	Old Bear Creek Rd PM 0.01	Other	This project will include: Slipout (20' W x 36' L) - Recommend WB Traveled Way and Shoulder Reconstruction, Drainage Improvements and Retaining Wall (Soldier Pile) Installation	2/2017	12/2020	6/2021	12/2027	17	29	50 Years	75 Years	No
Old Santa Cruz Hwy	PM 1.01	Old Santa Cruz Hwy PM 1.01	Other	Slipout (50'L) - NB/EB (Outboard) Traveled Way and Shoulder Reconstruction, Drainage Improvements and Retaining Wall (Soldier Pile) Installation	02/2017	4/2025	5/2025	12/2025	17	29	50 Years	75 Years	No
Old Santa Cruz Hwy	PM 1.06	Old Santa Cruz Hwy PM 1.06	Other	Slipout - NB/EB Traveled Way and Shoulder Reconstruction and Retaining Wall (Soldier Pile) Installation	02/2017	4/2025	5/2025	12/2025	17	29	50 Years	75 Years	No
Old Santa Cruz Hwy	PM 1.20	Old Santa Cruz Hwy PM 1.20	Other	This project will include: Storm Drain and/or Culvert Rehab/Repair (Existing)   Slipout (10' W x 50' L) - Recommend NB/EB Traveled Way, Drainage Improvements and Shoulder Reconstruction and Retaining Wall (Crib) Installation	02/2017	4/2025	5/2025	12/2025	17	29	50 Years	75 Years	No
Old Santa Cruz Hwy	PM 1.36	Old Santa Cruz Hwy PM 1.36	Other	This project will include: Storm Drain and/or Culvert Rehab/Repair (Existing)   Slipout (12' W x 90' L) - Recommend NB/EB (Outboard) Traveled Way and Shoulder Reconstruction and Retaining Wall (Soldier Pile) Installation	02/2017	4/2025	5/2025	12/2025	17	29	50 Years	75 Years	No
Paulsen Rd	PM 0.43	Paulsen Rd PM 0.43	Other	This project will include: Storm Drain and/or Culvert Rehab/Repair (Existing)	2/2017	12/2020	6/2021	12/2027	17	29	50 Years	75 Years	No
Prescott Rd	PM 0.52	Prescott Rd PM 0.52	Other	Slipout - NB Shoulder Reconstruction, Drainage Improvements and Retaining Wall (Crib) Installation	02/2017	4/2025	5/2026	12/2026	17	29	50 Years	75 Years	No
Redwood Dr	Oak Dr	REDWOOD DR @ OAK DR	Other	This project will include: Landscape Safety Installation (New)   40' long slipout on south side of culvert and failed section of cribwall undermining road on north side. Recommend rock slope protection backfill on one side and soil nail wall on other.	01/2023	02/2023	02/28/2023	12/2027	17	29	50 Years	75 Years	No
Redwood Dr	PM 0.19	REDWOOD DR PM 0.19	Other	This project will include: Landscape Safety Rehab/Repair (Existing).Pavement Improvement (New)  Storm Drain/Culvert Installation (New)   Culvert failure, undermining road. Recommend culvert replacement and adding headwalls	01/2023	02/2023	06/30/2023	12/2027	17	29	50 Years	75 Years	No
Redwood Lodge Rd	PM 1.80	Redwood Lodge Rd PM 1.80	Other	Culvert Failure and temp repair failure. Must be replaced with a bridge. Embankment reconstruction, excavation and backfill, concrete headwall, 120" culvert, erosion control and revegetation.	02/2017	3/2027	5/2027	12/2027	17	29	50 Years	75 Years	No
Redwood Lodge Rd	PM 2.02	Redwood Lodge Rd PM 2.02	Other	This project will include: Landscape Safety Rehab/Repair (Existing), Storm Drain and/or Culvert Rehab/Repair (Existing)   Preparation of design and environmental documents for large Slipout (30' W x 120' L) and Landslide - Recommend Roadway Reconstruction and Retaining Wall (Stitch Pile) Installation	03/2023	3/2027	5/2027	12/2027	17	29	50 Years	75 Years	No
Redwood Lodge Rd	PM 2.25	Redwood Lodge Rd PM 2.25	Other	Shoulder damage, 30' long, 2' into roadway. Recommend shoulder pile wall	02/2023	05/2026	06/2026	12/2026	17	29	50 Years	75 Years	No
Redwood Rd	PM 0.05	Redwood Rd PM 0.05	Other	30' long slipout halfway into road. Recommend shoulder pile wall with roadway reconstruction	02/2023	05/2025	06/2025	12/2025	17	29	50 Years	75 Years	No
Redwood Rd	PM 0.06	Redwood Rd PM 0.06	Other	This project will include: Cost Estimating, Document Preparation, Environmental Study/Documents, Preliminary Design	02/2023	05/2025	06/2025	12/2025	17	29	50 Years	75 Years	No
Redwood Rd	PM 0.15	Redwood Rd PM 0.15	Other	Slipout (50' L) - SB (Outboard) Traveled Way and Shoulder Reconstruction, Drainage Improvements and Retaining Wall (Soldier Pile) Installation	02/2017	5/2024	5/2024	08/2025	17	29	50 Years	75 Years	No

Exhibit A  
RMRA Project List for 2025/2026 Fiscal Year

Project Road	Project Location	Project Title	Project Type	Project Description	Pre-Construction Estimated Start	Pre-Construction Estimated Completion	Construction Estimated Start	Construction Estimated Completion	State Senate	State Assembly	Estimated Minimum Useful Life	Estimated Maximum Useful Life	Additional Project Elements
Redwood Rd	PM 0.23	Redwood Rd PM 0.23	Other	This project will include: Landscape Safety Rehab/Repair (Existing), Pavement Rehab/Repair (Existing), Storm Drain and/or Culvert Rehab/Repair (Existing)   Slipout (18' W x 35' L) - Recommend NB (Outboard) Shoulder Reconstruction, Drainage Improvements and Retaining Wall (Crib) Installation	02/2017	5/2024	5/2024	08/2025	17	29	50 Years	75 Years	No
Redwood Rd	PM 0.29, 0.31, 0.33	Redwood Rd PM 0.29, 0.31, 0.33	Other	PM 0.29 Roadway/Embankment Settling (120' L) Near Existing Retaining Wall - NB (Outboard) Shoulder Reconstruction and Retaining Wall (Soldier Pile) Installation, PM 0.31 Slipout (40' L) - NB (Outboard) Traveled Way and Shoulder Reconstruction, 18" Culvert, RSP and Retaining Wall (Soldier Pile) Installation, PM 0.33 Culvert Failure & Slipout (30' L) - NB (Outboard) Shoulder Reconstruction, Drainage Improvements including 18" Culvert	02/2017	05/2022	05/2022	08/2025	17	29	50 Years	75 Years	No
Redwood Rd	PM 0.38, 0.40	Redwood Rd PM 0.38, 0.40	Other	PM 0.38 Slipout (50' L) - NB (Outboard) Traveled Way and Shoulder Reconstruction, Drainage Improvements and Retaining Wall (Soldier Pile) Installation, PM 0.40 ULTRABLOCK Retaining Wall Failure - NB (Outboard) Shoulder Reconstruction, Drainage Improvements and Retaining Wall (Soldier Pile)	02/2017	4/2025	5/2026	12/2026	17	29	50 Years	75 Years	No
Redwood Rd	PM 0.97	Redwood Rd PM 0.97	Other	10' long by 7' tall shoulder slipout encroaching a foot into roadway. Recommend shoulder pile wall	02/2023	05/2026	06/2026	12/2026	17	29	50 Years	75 Years	No
Redwood Rd	PM 1.67	Redwood Road PM 1.67	Other	Damaged culvert and rowad shoulder from storms. Culvert replacement with headwalls	02/2023	05/2025	06/2025	12/2025	17	29	50 Years	75 Years	No
Rider Rd	PM 0.38	Rider Road PM 0.38	Other	35' long shoulder slipout above creek. RSP repair	02/2023	04/2023	06/30/2023	08/2025	17	29	50 Years	75 Years	No
Rider Rd	PM 0.40	RIDER RD PM 0.40	Other	This project will include: Landscape Safety Rehab/Repair (Existing)   Slipout along edge of road with undermining of roadway. Recommend rock slope protection backfill to stabilize slope.	01/2023	02/2023	02/28/2023	08/2025	17	29	50 Years	75 Years	No
Rider Rd	PM 0.80	Rider Road PM 0.80	Other	80' L slipout. Installing Soldier Pile Wall, Pavement and Shoulder Reconstruction	02/2017	4/2025	5/2025	12/2025	17	29	50 Years	75 Years	No
Rider Rd	PM 0.85	Rider Rd PM 0.85	Other	30' slipout along shoulder - RSP repair	02/2023	05/2026	06/2026	12/2026	17	29	50 Years	75 Years	No
Rider Rd	PM 1.38	Rider Rd PM 1.38	Other	slipout along shoulder, recommend RSP repair	02/2023	05/2026	06/2026	12/2026	17	29	50 Years	75 Years	No
San Andreas Rd	PM 1.24	SAN ANDREAS RD PM 1.24	Other	This project will include: Landscape Safety Installation (New), Pavement Improvement (New), Storm Drain/Culvert Installation (New)   Slipout (20' W x 40' L) - Recommend SB Shoulder Reconstruction, Drainage Improvements and Retaining Wall (Soldier Pile) Installation	02/2017	05/2025	05/2025	12/2025	17	29	50 Years	75 Years	No
San Andreas Rd	PM 2.14	SAN ANDREAS RD PM 2.14	Other	Failed 36-inch culvert due to storm flows. Replace culvert and catch basin	02/2017	05/2025	05/2025	12/2025	17	29	50 Years	75 Years	No
San Lorenzo Way	San Lorenzo River	San Lorenzo Way Bridge	Bridge Structure Repair/Rehab (Existing)	Replace Existing Bridge	02/2017	4/2025	5/2025	12/2025	17	29	50 Years	75 Years	No
Schulties Rd	PM 0.40	Schulties Rd PM 0.40	Other	This project will include repair of a Road edge slipout 80'	01/2021	3/2026	5/2027	12/2027	17	29	50 Years	75 Years	No
Schulties Rd	PM 1.14	Schulties Rd PM 1.14	Other	This project will include: Cost Estimating, Document Preparation, Environmental Study/Documents, Preliminary Design	2/2017	3/2025	6/2025	12/2025	17	29	50 Years	75 Years	No
Smith Grade Rd	PM 0.43	Smith Grade Rd PM 0.43	Other	This project will include: Pavement Rehab/Repair (Existing)   slipout/settlement pavement separation	02/2017	04/2022	01/2022	08/2025	17	29	50 Years	75 Years	No
Smith Grade Rd	PM 0.52	Smith Grade Rd PM 0.52	Other	This project will include: Storm Drain and/or Culvert Rehab/Repair (Existing)	02/2017	04/2022	06/2022	08/2025	17	29	50 Years	75 Years	No
Smith Grade Rd	PM 1.38	Smith Grade PM 1.38	Other	Road slump. Slurry and earth backfill repair	02/2017	04/2022	06/2022	08/2025	17	29	50 Years	75 Years	No
Smith Grade Rd	PM 1.90	Smith Grade Rd PM 1.90	Other	This project will include: Pavement Rehab/Repair (Existing)   3' diameter sinkhole	02/2017	04/2022	06/2022	08/2025	17	29	50 Years	75 Years	No
Smith Grade Rd	PM 2.83	Smith Grade Rd PM 2.83	Other	This project will include: Storm Drain and/or Culvert Rehab/Repair (Existing)	02/2017	04/2022	06/2022	08/2025	17	29	50 Years	75 Years	No
Smith Grade Rd	PM 4.06	Smith Grade Rd PM 4.06	Other	Slipout (25' W x 12' L) - EB (Outboard) Shoulder Reconstruction, Drainage Improvements and Retaining Wall (Soldier Pile) Installation	02/2017	4/2025	5/2025	12/2025	17	29	50 Years	75 Years	No
Soquel Drive	41st Ave	Soquel Dr to 41st Ave Dedicated Right Turn Lane	Other	Construct a dedicated right turn lane	01/2023	12/2025	02/2026	01/2027	17	29	50 Years	75 Years	No
Soquel Drive	Aptos Creek Rd.	Soquel Drive Aptos Creek Rd.	Traffic Control Devices	Install traffic signal, thermoplastic striping, railroad crossing, sidewalks, curb ramps, and drainage improvements	02/2017	05/2021	05/2021	12/2025	17	29	50 Years	75 Years	No
Soquel Drive	La Fonda Av to State	Soquel Drive Multimodal Project	Road Maintenance and Rehabilitation	Resurfacing, sidewalk, and bike lane improvements, striping	05/2021	06/2023	06/2023	12/1/2025	17	29	50 Years	75 Years	No
Soquel Drive	PM 0.80	Soquel Drive at Trout Gulch Road and Aptos Creek Road	Other	This project will include: Traffic Signals, Lights,	-	-	06/2019	12/2025	17	29	50 Years	75 Years	No
Soquel Drive	Robertson St.	Soquel Drive Robertson St.	Traffic Control Devices	Install traffic signal, thermoplastic striping and curb ramps	02/2017	06/2023	08/2024	07/2026	17	29	50 Years	75 Years	No
Soquel Drive	Soquel Ave	Soquel Dr to Soquel Ave Dedicated Right Turn Lane	Other	Construct a dedicated right turn lane	01/2023	12/2025	02/2026	01/2027	17	29	50 Years	75 Years	No
Soquel San Jose Rd	PM 1.25	Soquel San Jose Rd PM 1.25	Other	Slipouts - 60' long. soil nail retaining wall	2/1/2019	5/2024	5/2024	08/2025	17	29	50 Years	75 Years	No
Soquel San Jose Rd	PM 3.97	Soquel San Jose Rd PM 3.97	Other	This project will include: 2 slipouts, 20x50x10 & 50x150x10	2/1/2019	5/2024	5/2024	08/2025	17	29	50 Years	75 Years	No
Soquel San Jose Rd	PM 5.91	Soquel San Jose Rd PM 5.91	Other	This project will include: Landscape Safety Installation (New), Pavement Improvement (New)   Preparation of design and environmental documents for large Slipout (24' W x 115' L) - Recommend Roadway Reconstruction and Retaining Wall (TBD) Installation	2/1/2019	5/2024	5/2024	08/2025	17	29	50 Years	75 Years	No
Spanish Ranch Rl	PM 0.61	SPANISH RANCH PM 0.61	Other	This project will include: 20' long x 20' slipout, 2' into roadway. Recommend concrete retaining wall on piles.	01/2023	02/2023	05/31/2023	08/2025	17	29	50 Years	75 Years	No
State Park Dr	Santa Cruz Av, Broadway, Center Ave	State Park Dr at Santa Cruz Av, Broadway, & Center Ave	Safety	Constrcut Road, Roadside, Streetscape, Lighting and Landscape Improvements	05/2020	06/2025	08/2025	07/2026	17	29	50 Years	75 Years	No
Stetson Rd	PM 0.18	Stetson Rd PM 0.18	Other	Cribwall and culvert failure completely clsoing roadway. Replace culvert and construct new cribwall and roadway reconstruction	02/2023	05/2025	06/2025	12/2025	17	29	50 Years	75 Years	No
Stetson Rd	PM 1.08	Stetson Rd PM 1.08	Other	This project will include: Pavement Rehab/Repair (Existing), Storm Drain and/or Culvert Rehab/Repair (Existing)   Preparation of design and environmental documents for repair to slipout - 55L x 18D and install soldier pile wall	02/2023	05/2025	06/2025	12/2025	17	29	50 Years	75 Years	No
Stetson Rd	PM 1.29	Stetson Rd PM 1.29	Other	This project will include: Road edge failure, 30' long undermining guardrail. Recommend extending adjacent soldier pile wall.	02/2023	05/2025	06/2025	12/2025	17	29	50 Years	75 Years	No
Swanton Rd	PM 0.72	Swanton Rd PM 0.72	Other	8' Concrete Arch Culvert Failure and Slipout (64' L) - Temporary Creek Diversion System, SB Travelled Way and Shoulder Reconstruction and Retaining Wall (Soldier Pile) Installation	02/2017	4/2026	5/2026	12/2026	17	29	50 Years	75 Years	No

Exhibit A  
RMRA Project List for 2025/2026 Fiscal Year

Project Road	Project Location	Project Title	Project Type	Project Description	Pre-Construction Estimated Start	Pre-Construction Estimated Completion	Construction Estimated Start	Construction Estimated Completion	State Senate	State Assembly	Estimated Minimum Useful Life	Estimated Maximum Useful Life	Additional Project Elements
Stetson Rd	PM 1.29	STETSON RD PM 1.29	Other	This project will include: Road edge failure, 30' long undermining guardrail. Recommend extending adjacent soldier pile wall.	01/2023	02/2023	03/31/2023	08/2025	17	29	50 Years	75 Years	No
Swanton Rd	PM 3.00	Swanton Rd PM 3.00	Other	60' L slipout. Installing Soldier Pile Wall, Pavement and Shoulder Reconstruction	02/2017	4/2026	5/2026	12/2026	17	29	50 Years	75 Years	No
Swanton Rd	PM 5.27	SWANTON RD PM 5.27	Other	This project will include: Pavement Rehab/Repair (Existing)   200' long slipout. Recommend soldier pile wall and reconstruct portion of roadway	02/2023	02/2023	05/31/2023	08/2025	17	29	50 Years	75 Years	No
Trout Gulch Rd	PM 1.16	Trout Gulch Rd PM 1.16	Other	This project will include: Slipout (20' W x 40' L) - Recommend NB Traveled Way and Shoulder Reconstruction, Drainage Improvements and Retaining Wall (Soldier Pile) Installation	2/2017	12/2020	6/2021	12/2027	17	29	50 Years	75 Years	No
Trout Gulch Rd	PM 1.18	Trout Gulch Rd PM 1.18	Other	This project will include: Culvert Failure and Slipout (18' W x 25' L) - Recommend NB Traveled Way and Shoulder Reconstruction and 18' Culvert and Retaining Wall (Soldier Pile) Installation	2/2017	12/2020	6/2021	12/2027	17	29	50 Years	75 Years	No
Trout Gulch Rd	PM 1.85	Trout Gulch Rd PM 1.85	Other	This project will include: Slipout (20+/-' W x 50' L) - Recommend SB Traveled Way and Shoulder Reconstruction, RSP, and Retaining Wall (Soldier Pile) Installation	2/2017	12/2020	6/2021	12/2027	17	29	50 Years	75 Years	No
Trout Gulch Rd	PM 1.90	Trout Gulch Rd PM 1.90	Other	This project will include: Large Slipout (40+/-' L) Near Existing Cross Culvert - Recommend SB Traveled Way and Shoulder Reconstruction, 18' Culvert, RSP, and Retaining Wall (Soldier Pile) Installation	2/2017	12/2020	6/2021	12/2027	17	29	50 Years	75 Years	No
Trout Gulch Rd	PM 3.05	Trout Gulch Rd PM 3.05	Other	This project will include: Slipout (15+/-' W x 20' L) - Recommend NB Traveled Way and Shoulder Reconstruction, Drainage Improvements and Retaining Wall (Crib) Installation	2/2017	12/2020	6/2021	12/2027	17	29	50 Years	75 Years	No
Trout Gulch Rd	PM 2.90	TROUT GULCH PM 2.90	Other	This project will include: Storm Drain/Culvert Installation (New)   Sink holes above culvert. Approx 48' culvert. Recommend culvert replacement with headwalls	02/2023	04/2023	06/30/2023	08/2025	17	29	50 Years	75 Years	No
Two Bar Rd	PM 1.13	Two Bar Rd PM 1.13	Other	This project will include: Storm Drain and/or Culvert Rehab/Repair (Existing)   Slipout (40' W x 65' L) - Recommend NB/EB Traveled Lane and Shoulder Reconstruction, Drainage Improvements and Retaining Wall (Soldier Pile) Installation	2/2017	12/2020	6/2021	12/2027	17	29	50 Years	75 Years	No
Upper East Zayante Rd	PM 0.51	UPPER ZAYANTE PM 0.51	Other	This project will include: Storm Drain/Culvert Installation (New)	02/2023	04/2023	04/30/2023	08/2025	17	29	50 Years	75 Years	No
Upper East Zayante Rd	PM 1.18	Upper East Zayante Rd PM 1.18	Other	Road edge slipped out from clogged bleeder, tree failure with shoulder damage. Recommend shoulder pile wall and roadway reconstruction	02/2023	05/2026	06/2026	12/2026	17	29	50 Years	75 Years	No
Upper East Zayante Rd	PM 1.68	Upper East Zayante PM 1.68	Other	Slipout (45' L) Near Existing Retaining Wall (Crib) and Landslide - SB Traveled Way and Shoulder Reconstruction, Drainage Improvements and Retaining Wall (Soldier Pile) Installation	02/2017	4/2025	5/2025	12/2025	17	29	50 Years	75 Years	No
Upper East Zayante Rd	PM 2.51	Upper East Zayante Rd PM 2.51	Other	30' long shoulder slipout. Recommend soldier pile repair	02/2023	05/2025	06/2025	12/2025	17	29	50 Years	75 Years	No
Upper Zayante Rd	PM 3.51	UPPER ZAYANTE PM 3.51	Other	This project will include: Pavement Rehab/Repair (Existing),Storm Drain/Culvert Installation (New)   culvert replacement with rsp slope repair, 75' of paving	02/2023	04/2023	04/30/2023	08/2025	17	29	50 Years	75 Years	No
Valencia Rd	PM 0.04	VALENCIA RD PM 0.04 (Trout Creek)	Other	This project will include: Pavement Rehab/Repair (Existing)   9' Culvert Failure and Roadway/Embankment Settling - Recommend Installation of Temporary Bridge, Replacement of Existing Culvert with a Box Culver and Roadway Reconstruction	2/2017	12/2020	6/2021	12/2027	17	29	50 Years	75 Years	No
Valencia Rd	PM 0.25	Valencia Rd PM 0.25	Other	Large slipout from above. Road damage about 50 long by 15' deep undermining edge of road and guardrails. Shoulder pile wall repair	02/2023	05/2025	06/2025	12/2025	17	29	50 Years	75 Years	No
Valencia Rd	PM 0.33	VALENCIA RD PM 0.33	Other	This project will include: Landscape Safety Rehab/Repair (Existing)   Erosion at pipe discharge. Material moving down to the creek. Recommend slope repair and placement of rock slope protection	03/2023	06/2023	03/31/2023	08/2025	17	29	50 Years	75 Years	No
West Zayante Rd	PM 0.25	W ZAYANTE PM 0.25	Other	This project will include: Storm Drain and/or Culvert Rehab/Repair (Existing)	02/2023	04/2023	04/30/2023	08/2025	17	29	50 Years	75 Years	No
Zone 5	All Roads	Road Drainage Master Plan Study - Zone 5 roads	Other	Road Drainage Master Plan Study - Zone 5 roads	05/2020	07/2026	-	-	17	29	50 Years	75 Years	No